Dedicated to enhancing and preserving a rural lifestyle



August 17, 2013

TO: Mark Slovick, Planning Manager, Lilac Hills Ranch Project Department of Planning & Development Services County of San Diego

FROM: The Bonsall Community Sponsor Group

RE: Accretive Investment Group proposal DEIR –DEIR Public Comment to the Proposed Accretive Lilac Hills Ranch General Plan Amendment and Specific Plan PDS2012-3800-12-001(GPA),PDS2012-3810-12-001 (SP)

GENERAL PLAN CONSISTENCY ANALYSIS

Introduction:

In comments submitted over the last year, the Bonsall Sponsor Group and the Bonsall Design Review Board have challenged the applicants assertions that this SP/GPA is consistent with the adopted County General Plan [GP], or with Bonsall's Community Plan [CP], or with Bonsall Design Guidelines. Our previous comments, which are attached, have also challenged the logic exhibited throughout Accretive Investment Group's Specific Plan and now in their Draft Environmental Impact Report: that amending a particular GP Regional Category to suit the project somehow also reconciles the project's inconsistencies with a wide array of General and Community Plan Goals and Policies.

We believe the proposed SP/GPA is inconsistent with the County's General Plan and the Community Plans of both Bonsall and Valley Center, as well as with a number of other adopted planning documents. Further, we think the <u>DEIR fails to disclose these broad and fundamental inconsistencies and is derelict in concluding that "Overall the project would be consistent with the General Plan; therefore land use impacts associated with policy inconsistencies would be less than significant" (Chapter 3 Environmental Effects Found Not To Be Significant (p 3-65).</u>

The California Environmental Quality Act (CEQA) requires a General Plan consistency analysis and supportable conclusions. How can the DEIR conclude that planning impacts are 'insignificant' without these analyses?

This DEIR fails to perform the analyses required for decision makers, first, to understand the parameters of this proposal, and, second, to appreciate the nature and reach of its impacts. Why?

Internal consistency of all County General Plans in California is required by California State Law. Therefore, in considering a Specific Plan, particularly one that requires amendments to an adopted General Plan, it is crucial to understand exactly where the Specific Plan is inconsistent with General Plan regional categories, land use designations and road classifications, principles, elements, goals and policies. *Why was this not done?*

A Specific Plan is an implementation vehicle. Approval requires consistency with CEQA; consistency as well with the web of interconnected and mutually-supporting elements of the County General Plan, and consistency with the array of implementation actions, strategies and procedures that are in place to achieve the goals and policies that the General Plan sets forth. Inconsistency requires denial of the project OR adapting the General Plan to fit the Specific Plan – the tail wagging the dog. Broad and fundamental amendments to adopted General and Community plans would require county-wide environmental review when will this be done?



Dedicated to enhancing and preserving a rural lifestyle



We all can understand why the applicants might want to avoid disclosing the array of GP and CP Goals and Policies that this project violates. But CEQA's purpose is not to gloss over or obscure inconsistencies in order to ease approval of this project. CEQA's purpose is disclosure.

Therefore, the DEIR for this SP/GPA must reckon specifically and individually with the General Plan Vision and Guiding Principles and the reflection of these in the Community Development Model, as well as with Goals and Policies across the GP's seven elements: Land Use, Mobility, Conservation and Open Space, Housing, Safety and Noise; as well as goals and policies of the Bonsall and Valley Center Community Plans.

Once inconsistencies are disclosed there are only three ways to resolve them: reject the project, re-design the project, or re-build the County General Plan to suit these applicants. Is this the goal of this project?

Inconsistencies with General and Community Plans, Design Guidelines and other ordinances and policies are NOT subordinate to this project's Specific Plan, as the Specific Plan asserts. Why was this statement circulated in the DEIR?

- 1. Why is there NO GENERAL PLAN AMENDMENT REPORT? Nowhere is there analysis of this project's consistency with GP Goals and Policies. There are CLAIMS of GP "conformance" but no data to support them WHY? Where is the data to support claims of GP conformance?
- 2. Why does this proposal fail to meet the LEED Neighborhood Development (LEED-ND)PRE-REQUISITE location criteria? This will be mentioned several times in this document to be answered by staff.

LEED ND cites as key smart growth strategies the building on previously constructed development sites or 'infill' sites [surrounded or mostly surrounded by previously developed land]. When a smart growth site is selected, there is no additional loss of biological habitat or excessive land gouging. For this Project, LEED ND was not respected nor observed why? Why was LEED ND neither observed nor respected as a selected "smart growth" site?

Oddly, the County General Plan recognizes the importance of LEED ND criteria and cites them as part of its principles. But, the DEIR and the applicant has subverted them in this case. What was the reason that the DEIR did not analyze the Project in terms of its consistency with LEED ND? Given that, this project is a "leapfrog development, it must be certified as consistent with LEED ND requirements or its equivalent? If using an equivalent standard for certification, what is the equivalent standard?

- 3. Why is it that Valley Center and Bonsall bear more than a fair share of San Diego County General Plan growth even before the addition of the proposed Lilac Hills Ranch project?
 - a. The General Plan growth in housing units across the entire County of San Diego is summarized in Table X-Y below. Table X-Y San Diego County General Plan Housing Unit Forecast 2010-2050





Dedicated to enhancing and preserving a rural lifestyle



Bonsall Housing Units as reflected in the August 2011 General Plan are growing 59% from 2010 to 2050, **nearly 2 times** the rate of the County overall.

This project has suggested changes to our Bonsall Community Plan that support a new town center designation in an area designated as agricultural in our community plan. We followed the goals of the General Plan by placing our density where sewer service and all of our current density planning is designated. Why would the county approve a plan that does not support our established goals by placing a community center outside of our current community plan? This project is a 'COMMUNITY BUSTER" and a "growth inducer" that is not supported in the General Plan or the Community Plan why is this allowed?

Growth is also planned at the traditional town center, close to the intersection of SR-76 and Mission Road, where necessary infrastructure for dense, urban development is in either on the ground or planned (and funded) to be added shortly. This project has the ability to change the Bonsall Community Plan and create a second town center on our boundary with Valley Center where we have designated a buffer of large lots and agriculture. Why should this project be allowed to change the Bonsall Community Plan with this designation? What about future landowners that can no long use their land for agriculture and sell to other developers that want to create more density and another town center? Why bother with a community plan if developers can subvert it to whatever they want with little regard to the communit?

The combined composite effects of adding Lilac Hills Ranch in addition to General Plan growth is provided in Table Y-Z below:

Tab	Table Y-Z Bonsall and Valley Center Composite Housing Unit Analysis							
					% Grov	% Growth from 2		
	Housing Un	its			2010	2020	2010 t0	
					to	to		
	2010	2020	2030	2050	2020	2030	2050	
Bonsall	3,875	4,320	5,149	6,151	11.5%	19.2%	58.7%	
Valley Center	6.638	7.627	9.795	13.411	14.9%	28.4%	102.0%	
Subtotal General Plan	10,513	11,947	14,944	19,562	13.6%	25.1%	86.1%	
Lilac Hills Ranch (LHR)		746	1,746	1,746				
Total with LHR included	10,513	12,693	16,690	21,308	20.7%	31.5%	102.7%	
Reference: SD County growth	1,158,076	1,262,488	1,369,807	1,529,090	9.0%	8.5%	32.0%	





Dedicated to enhancing and preserving a rural lifestyle



The chart below is Bonsall's population growth/density without Lilac Hills Ranch.

		Housin	g Units		Percent Change				
CPA	2010	2020	2030	2050	2010- 2020	2020- 2030	2030- 2050	2010-50	
Alpine	6,535	6,690	7,875	9,157	2.4%	17.7%	16.3%	40.1%	
Barona	202	170	170	170	-15.8%	0.0%	0.0%	-15.8%	
Bonsall	3,875	4,320	5,149	6,151	11.5%	19.2%	19.5%	58.7%	
Central Mountain	2,182	2,305	2,589	2,735	5.6%	12.3%	5.6%	25.3%	
County Islands	614	607	607	635	-1.1%	0.0%	4.6%	3.4%	
Crest-Dehesa	3,562	3,677	3,926	3,978	3.2%	6.8%	1.3%	11.7%	
Desert	3,546	3,453	4,337	6,923	-2.6%	25.6%	59.6%	95.2%	
Fallbrook	15,929	16,535	18,559	20,387	3.8%	12.2%	9.8%	28.0%	
Jamul-Dulzura	3,234	3,372	4,398	5,263	4.3%	30.4%	19.7%	62.7%	
Julian	1,711	1,748	1,884	2,015	2.2%	7.8%	7.0%	17.8%	
Lakeside	27,575	28,517	30,339	30,915	3.4%	6.4%	1.9%	12.1%	
Mountain Empire	3,023	3,056	3,903	5,108	1.1%	27.7%	30.9%	69.0%	
North County Metro	16,114	19,548	24,090	25,946	21.3%	23.2%	7.7%	61.0%	
North Mountain	1,527	1,759	2,002	2,388	15.2%	13.8%	19.3%	56.4%	
Otay	7	490	2,035	2,156	6900.0%	315.3%	5.9%	30700.0%	
Pala-Pauma	1,980	2,285	3,037	4,399	15.4%	32.9%	44.8%	122.2%	
Pendleton-De Luz	7,531	8,533	8,684	8,797	13.3%	1.8%	1.3%	16.8%	
Rainbow	708	750	881	963	5.9%	17.5%	9.3%	36.0%	
Ramona	12,376	12,692	14,107	15,140	2.6%	11.1%	7.3%	22.3%	
San Dieguito	10,993	11,053	11,924	13,601	0.5%	7.9%	14.1%	23.7%	
Spring Valley	20,533	20,939	21,837	21,952	2.0%	4.3%	0.5%	6.9%	
Sweetwater	4,670	4,657	4,732	4,732	-0.3%	1.6%	0.0%	1.3%	
Valle De Oro	15,543	15,648	16,022	15,968	0.7%	2.4%	-0.3%	2.7%	
Valley Center	6,638	7,627	9,795	13,411	14.9%	28.4%	36.9%	102.0%	
Unincorporated Area	170,608	180,431	202,882	222,890	5.8%	12.4%	9.9%	30.6%	
San Diego County	1,158,076	1,262,488	1,369,807	1,529,090	9.0%	8.5%	11.6%	32.0%	

SOURCE: SANDAG Profile Warehouse: 2050 Forecast

FIRE PROTECTION PLAN (FPP)

Why doesn't the proposed Lilac Hills Ranch (LHR) Project FPP meet the following basic requirements identified below by Issue Number?

- 1. Of the three Fire Station site Options proposed by the Applicant, none meet the minimum acceptance criteria of the Deer Springs Fire Protection District (DSFPD). The Charter of the DSFPD focuses on providing no greater than 5 minute emergency response time to the ENTIRE DSFPD, of which the proposed LHR Project is a subset. *WHY is this allowed?*
- 2. The Applicant states in the FPP that the LHR Project fully complies with the DSFPD Ordinance No. 2010-01, County of San Diego Consolidated Fire Code, and County of San Diego Public and Private Road Standards. The LHR has factual compliance issues with all of these regulations. WHY is this allowed?





Dedicated to enhancing and preserving a rural lifestyle



- 3. The FPP focuses nearly exclusively on Wildfire Management and does not sufficiently address either Structure Fires or Emergency Medical Service (EMS) *WHY?*
- 4. The FPP doesn't adequately address and analyze the Environmental Impact of the use of six electronic road gates on fire access roads **WHY?**
- **5.** Fuel Modification Zones (FMZ) The applicant appears to rely on other property owners outside the LHR Subdivision boundaries to comply with the 100 foot FMZ requirement **WHY?**

Each of the five Issues above is substantiated as follows.

Issue 1 – Acceptable siting Options for a Fire Station servicing the LHR Project - The following information has been synthesized from (documents provided by the Valley Center Planning Group in their submittal) the 6/12/13 (Attachment A), 3/5/2013 (Attachment B), and 8/7/2013 (Attachment C) DSFPD Letters. In addition, Valley Center Community Planning Group members had a 2 hour meeting with Chief Amestoy as well as telephone conversations with respect to Environmental Impacts of the proposed LHR Project. Information from these interchanges are reflected below and included in the Valley Center submittal.

- The DSFPD Charter is to provide Fire and EMS services for the entire District, including the potential LHR Project.
- -DSFPD owns three fire stations (Station 11- 8709 Circle R Drive, Escondido; Station 12 at 1321 Deer Springs Road, San Marcos; and Station 13 at 10308 Meadow Glen Way East, Escondido.

HAZARDOUS MATERIALS AND WILD FIRES

The present plan appears to ignore buffering of neighboring agricultural operations completely. This Project is replete with sensitive receptors such as schools, parks, homes, a church and a senior assisted living facility. Does the applicant anticipate that the County will impose buffer areas on the surrounding agricultural operations after approval of the Project? Have the surrounding agricultural operations been notified that their operations may be significantly impacted if buffering is imposed on them rather than the applicant?

Policy S-11.5 seems to put the burden of buffering on the applicant, not the existing agricultural operations. Will this be one of the General Plan policies that will be changed to accommodate the Project at the expense of established agriculture? A reasonable analysis of the buffering requirement would conclude that buffering surrounding agricultural operations from the Project presents a significant impact to existing agriculture. The applicant's "Analysis of Project Impacts and Determination of Significance," [2.7.2] points to how significant this impact is:

The project would result in a significant impact if it would:

1. Hazardous Substance Handling: Create a significant hazard to the public through the use of hazardous substances.

While the applicant's intention was to discuss the applicant's proposed on-site handling of hazardous materials, that discussion should have also included the issue of buffering the application of pesticides, herbicides, fungicides, amendments and fertilizers by existing agricultural operations. More than one operation adjacent to the Project uses helicopters to apply agricultural chemicals to broad swaths of orchards and fields. Overspray could be an issue if not properly buffered. How will the applicant address this CEQA mandatory finding of significance? Will the allowance of less than 100 ft buffer in the Bonsall area require existing agricultural to deal with the additional buffer impact?????





Dedicated to enhancing and preserving a rural lifestyle



- EMERGENCY RESPONSE AND EVACUATION PLANS

The DEIR cites the Operational Area Emergency Plan and the Multi-Jurisdictional Hazard Mitigation Plan as mechanisms or protocols that would mitigate cumulative impacts to emergency response and evacuation plans. The DEIR fails to address those problems from the Valley Center or Bonsall community perspectives. The mobility element roads nearest the Project are West Lilac Road and Circle R Road. Both of those roads were built to serve a rural community with small, rural populations. *How did this failed plan pass county staff?*

In the event of an emergency evacuation, such as occurred in 2003 and 2007, much of the population of Valley Center and Bonsall existing population will be exiting to the Interstate-15 corridor and Highway 76 all at once, not just the residents of the proposed Project. While the Operational Area and Multijurisdictional plans may help to organize first responders and emergency personnel, the congestion on the limited number of mobility element roads will be intense and long lasting and will affect both evacuees and emergency personnel, who are generally headed in both easterly and a westerly direction. Such congestion could result in serious harm to thousands of people if a fire should overtake them while trapped in traffic. How was this proven evacuation problem not considered? If considered then why was this project allowed to go forward as submitted?

Why would the County allow the applicant to propose to further exacerbate that bad situation by asking for 10 road standard modifications that would lower the classification of the mobility element roads in some cases, and lower the design speeds of those roads. The Bonsall Sponsor Group does not support lowering standards and would find the issue of liability that the County will take on with this project a folly of great magnitude? With lower design speeds and narrower roadways, this Project will imperil the evacuation of the Valley Center and Bonsall existing residents and impede the prospective residents of the Project at the same time. Such a large urban Project located in a rural setting with limited mobility options could single-handedly, never mind cumulatively, severely and significantly put hundreds of people at risk in the event of a large scale fire like those experienced in 2003 and 2007.

WILD LAND FIRES

The location of urban densities adjacent to a 'very high FHSZ' does not present itself as a smart location consistent with preventative land use planning. The present General Plan incorporates land use and zoning designations that concentrate high-density housing at the core of the Valley Center and Bonsall communities. Such high densities were not planned for the margins of the two communities. Those areas were intentionally planned for large acreages to accommodate agricultural pursuits according to the Community Development Model. WHY would the General Plan be allowed to be subverted by this developer financial gain and allowed to change the General Plan?

If approved, this Project will defeat the intent of the Community Development Model by locating a dense urban development away from the village cores of Bonsall and Valley Center in an area prone to very high wildfire hazards. Why hasn't the applicant overlain the Fire Hazard Severity Zones on a Project map to indicate the locations of the very high FHSZ. Such a map would allow a more informed evaluation of the probable risks to the Project and surrounding properties and how those risks should be handled. Such information is crucial to decision-makers?





Dedicated to enhancing and preserving a rural lifestyle



This paragraph also relates to Emergency Response and Evacuation Plans as noted on previous page.

The mitigation proposed is to acquire an easement on adjacent property that is not a part of the Project so the FMZ can be extended to the full 100-feet. Why would this be allowed?

Barring that, the applicant proposes to use ignition resistant construction methods and other non-combustible features to purportedly achieve the same level of fire resistance as the 100-foot FMZ. Presuming such construction techniques could work, one would think that the applicant would employ them regardless of the deficient FMZ simply because it's a safer course when building at the wildland-urban interface. Has the applicant considered prudent course of modifying the configuration of those portions of the Project in those very high FHSZ to accommodate the standard FMZ?

A Project of this density and design is inappropriate at this location regardless of building standards and fuel modification plans given the proximity to dense on-site and off-site native fuels [the WUI very high FHSZ], the inconsistent use of a standard 100-foot FMZ, the inadequate evacuation routes for over 5000 residents and the uncertainty surrounding how will fire protection services will be provided please define?

MANDATORY FINDINGS

The California Legislature has determined that certain specified changes to the environment are significantly adverse by definition. These are often called mandatory findings of significance. As a result of the legislature's determination a lead agency must conclude that a proposed project may have a significant effect on the environment if the project does any of the following:

- 1. Has the potential to degrade substantially the quality of the environment;
- 2. Has the potential to achieve short-term environmental goals at the expense of long-term environmental goals;
- 3. Has potential environmental effects that are individually insignificant but cumulatively considerable;
- 4. Has the potential to cause substantial adverse direct and indirect impacts on human beings;
- 5. Has the potential to eliminate important examples of major periods of California prehistory or history;
- 6. Has the potential to change adversely the sgnificance of a designated historical structure;
- 7. Has the potential to reduce substantially the habitat of fish or wildlife species;
- 8. Has the potential to cause a fish or wildlife population to drop below self-sustaining levels;
- 9. Has the potential to threaten or eliminate a plan or animal community; or,
- 10. Has the potential to substantially reduce the number or restrict the range of an endangered, rare, or threatened species.

How does the County justify moving forward after reading the California Legislature mandatory findings of <u>significance</u> and reviewing the 268 page "PROJECT ISSUE CHECKLIST" created by staff?

How did staff determined that several of the 10 mandatory findings have not caused this project to be rejected upon submission?





Dedicated to enhancing and preserving a rural lifestyle



Staff identified in the Scoping Letter/Project Issue Checklist one-hundred twenty-one (121) GP Policy conflicts and one-hundred seventy-four (174) policy conflicts in the Bonsall and Valley Center Community Plans and the General Plan. These have not been analyzed in the DEIR (or anywhere else). Why not?

Earlier in the review of this project a "Project Issue Checklist" listed (on 350-plus pages) more than 1000 project "issues" with various planning documents. The list included Major Project Issues (with GP Policies) as well as GP and CP Policies that posed potential conflicts. Analyses of these "issues" are essential to a General Plan Amendment. How else can anyone understand what the GPA proposes to amend?

The staff directive to the applicant at that time was, "Please immediately review the policies and indicate to staff how you would propose to revise these policies or if you disagree with staff's analysis. If policy revisions are required to the County's General Plan, then the project's EIR must also analyze the impacts to the County's General Plan." In subsequent editions, the "Checklist" refers the reader to other documents – in some instances to a GPAR (General Plan Amendment Report), in others to the Land Use Section of the EIR. Where is the report that is mentioned in both documents?

CEQA requires these analyses, and the DEIR omits them. The DEIR (in Section 3.1.4.1, pp 3-56 – 3-64) lists what it calls the "relevant policy and regulatory framework" for the project. But this list is not the detailed analyses that CEQA requires; instead, under the rubric of "Existing Conditions" this section is mainly a summary of applicable planning documents. **WHY has staff taken this point of omitting relevant policy and regulatory framework?**

Examples are rife, here are a few:

Section 3.1.4.2 (p 3-64) is titled "Analysis of Project Impacts and Determination of Significance." Here in the subsection "*Impact Analysis*" analyses of specifics are either missing or inadequate, and replaced with brief descriptions of the project followed by assertions. Such as:

- a. Without bothering even to acknowledge the array of GP policies that would have to change in order to approve this SP/GPA, the DEIR concludes: "The proposed project includes a General Plan Amendment which, if approved, would result in the project being consistent with the General Plan."

 It is not consistent with the General Plan and that is a fact Why the double speak?
- **b.** There is no discussion of LEED ND criteria, and the GP Community Development Model is presented as if it is no more than an arrangement of densities rather than a reflection of a whole complex of interdependent ideas about sustainable development. Nevertheless, the DEIR asserts that "the proposed project would be consistent with the Community Development Model of the County General Plan and designed to meet the LEED Neighborhood Development Certification or an equivalent." **How is this possible please explain?**
- c. The policy is in some cases asserted by repeating the language of the policy itself. For LU1.2: "the project is not "leap frog development" because it is designed to conform to the Community Development Model, provides necessary services and facilities, and would be designed to meet the LEED Neighborhood Develop Certification or an equivalent.





Dedicated to enhancing and preserving a rural lifestyle



For LU3-1, LU3-2 and LU3-3: "The project likewise provides "a complete neighborhood" to include a neighborhood center within easy walking distance of surrounding residences while providing a mixture of residential land use designations and development regulations that accommodate various building types and styles."

d. In a few cases where the SP/GPA proposes amendments to Mobility Element road classifications or acceptable LOS levels, the DEIR argues that the SP/GPA is not inconsistent with the GP because relaxing the standards makes it consistent. Again, the point here is that consistency is achieved only by amending the General Plan to fit the project.

Please review what a LEED ND project is (below) and then what was written by the applicant and staff (above) as this project does not demonstrate the definition of what a LEED ND is. Why was this project allowed to go through the county process with this as a basis?

LEED ND cites as key smart growth strategies the building on previously constructed development sites or 'infill' sites [surrounded or mostly surrounded by previously developed land]. When a smart growth site is selected, there is no additional loss of biological habitat or excessive land gouging. For this Project, LEED ND was not respected nor observed why? Why was LEED ND neither observed nor respected as a selected "smart growth" site?

Oddly, the County General Plan recognizes the importance of LEED ND criteria and cites them as part of its principles. But, the DEIR and the applicant has subverted them in this case. What was the reason that the DEIR did not analyze the Project in terms of its consistency with LEED ND? Given that, this project is a "leapfrog development, it must be certified as consistent with LEED ND requirements or its equivalent? If using an equivalent standard for certification, what is the equivalent standard?

In a few cases where the SP/GPA proposes amendments to Mobility Element road classifications or acceptable LOS levels, the DEIR argues that the SP/GPA is not inconsistent with the GP because relaxing the standards makes it consistent. Again, the point here is that consistency is achieved only by amending the General Plan to fit the project Why?

The DEIR (Section 3.1.4, p 3-56, Land Use Planning, line 4) refers the reader to the Specific Plan, and asserts falsely (p. 3-65) that "the project's conformance with other General Plan policies is detailed in the Specific Plan. Overall the project would be consistent with the General Plan; therefore land use impacts associated with policy inconsistencies would be less than significant." Please explain how the overall project would be consistent with the General Plan?

It is important to note here that these analyses are NOT in the Specific Plan or a GPAR, even though this would be no substitute for the CEQA requirement. The *Specific Plan* text does NOT include a *General Plan Amendment Report* (GPAR). Historically, a GPAR presents the details of a GPA and discusses its consistency, or lack of consistency, with GP elements. But, this application omits this crucial report. *Why? I mentioned this question both on the phone and before in this document?*





Dedicated to enhancing and preserving a rural lifestyle



The DEIR fails to disclose the extent to which this SP/GPA is inconsistent with the County's planning documents. Land use impacts are much broader and more fundamental than what has been disclosed. Amendments to suit this SP/GPA would require rejecting the GP's foundational vision: Smart Growth. How is this to be achieved?

As stated it is not the intention of the San Diego General Plan to drop "new villages" into semi-rural and rural areas. To the contrary, the County General Plan is rooted in its "Smart Growth" intention. Smart Growth is a two-sided concept. On the one hand Smart Growth locates future development in areas where infrastructure is established; AND on the other hand, Smart Growth also retains or enhances the County's rural character, economy, environmental resources, and unique communities. These are integrated, co-dependent concepts. They work together.

How does this project of 5000 people of approximately 608 acres of infrastructure-lacking Semi-Rural and Rural land become consistent with both interdependent aspects of Smart Growth as they are expressed across and interconnected with the web of GP Guiding Principles, Goals and Policies that have been put in place to bring about the County's Smart Growth Vision?

The DEIR asserts that the project is consistent with the GP Community Development Model and with LEED Neighborhood Development Certification standards. The proposal fails to meet essential requirements of both.

As listed before in this document the definition of LEED ND and what has been submitted by the applicant do not agree. Why has staff accepted this project under this guise?

1. The General Plan already accommodates more growth than SANDAG projects for 2050. The DEIR fails to justify the need for 1746 additional homes, 90,000 additional SF of commercial.

Consistency with Land Use Goal 1 (LU-1) and Policy 1.2 (LU 1.2) are especially crucial for this project's approval. This goal and policy speak directly to the requirements for establishing NEW villages in San Diego County. *How does this project meet the Land Use Goal or the Policy?*

Land Use Goal 1: Primacy of the Land Use Element. A land use plan and development doctrine that sustain the intent and integrity of the Community Development Model and the boundaries between Regional Categories.

Land Use Policy 1.2: Leapfrog Development. Prohibit leapfrog development which is inconsistent with the <u>Community Development Model</u>. Leapfrog Development restrictions do not apply to new villages that are designed to be consistent with the Community Development Model, that provide necessary services and facilities, and that are designed to meet the <u>LEED Neighborhood Development Certification</u> or and equivalent. For purposes of this policy, leapfrog development is defined as Village densities located away from established villages or outside established water and sewer service boundaries. (See applicable community plan for possible relevant policies.)

This SP/GPA is INCONSISTENT with both the Community Development Model and with LEED Neighborhood Development Certification Standard. (No LEED ND "equivalent" has been developed to our knowledge; nor is one cited in the Specific Plan or the DEIR. By definition an "equivalent" standard would have to include LEED ND's location prerequisite or it would *not* be an equivalent standard).





Dedicated to enhancing and preserving a rural lifestyle



Inconsistent with LEED Neighborhood Development Certification standards and Inconsistent with the Community Development Model

The General Plan states (San Diego County General Plan: Land Use Framework; Community Development Model, p.3-6): "The Community Development Model directs the highest intensities and greatest mix of new uses to Village areas, while directing lower-intensity uses such as estate-style residential lots and agricultural and agricultural operations to Semi-Rural areas To facilitate a regional perspective the Regional Categories of Village, Semi-Rural and Rural Lands have been applied to all privately-owned lands ..."

First, as the above statement in the County General Plan makes clear, the Community Development Model is *not* a moveable abstract concept. If this were true then Village "puzzle pieces" could be dropped into Semi-Rural and Rural lands anywhere in the County and pronounced consistent with the Community Development Model. *How did this project pass the Community Development Model* as it is not consistent and is located in a semi-rural area of the County?

Rather, the Community Development Model reflects a complex of planning principles and ideas that are expressed through the General Plan's Regional Categories. It is the assignment of a particular Regional Land Use Category to a particular piece of land that this SP/GPA proposes to amend. The proposal therefore is inconsistent with the Community Development Model. *Again, consistency would be achieved only by amending the General Plan to fit the project. Why?*

- In the General Plan (p 3-7) "Village areas function as the center of community planning areas and contain the highest population and development densities. Village areas are typically served by both water and wastewater systems. Ideally, a Village would reflect a development pattern that is characterized as compact, higher density development that is located within walking distance of commercial services, employment centers, civic uses, and transit."
- The proposed site is designated not for Village development but for large semi-rural parcels (SR 10 and SR-4). This proposal to plop a Village into the middle of an area that the Community Development Model designates for Semi-Rural and Rural development requires AMENDING the Community Development Model. Why was this not done? If the General Plan is to be unusable by developers as it is after 13 years of work then why have it?
- This SP/GPA is located many miles from areas that the Community Development Model designates for Village development: miles from employment centers, shopping, entertainment, medical services, and civic organizations and activities and transportation. *How does this project meet any of the LEED-ND or "smart growth" ideals?*
- As for infrastructure, there are few existing roads in the area and they are built and planned to service Semi-Rural and Rural development, as is the current plan. Despite proposing intense Village development, the proponents also propose to retain or reduce capacities of these roads.
- With an additional total of cars based on the Counties 10 trips a day per household and the current traffic on this two lane road how does this money maker for the developer plan to abate/mitigate the traffic?





Dedicated to enhancing and preserving a rural lifestyle



- The intent of the Community Development Model for Villages is to intensify development in existing Villages -- not to create NEW Villages through the destruction of Semi-Rural and Rural lands. The Community Development Model was applied in Bonsall during the General Plan update process. Village boundaries were drawn. Village densities were planned to feather from the commercial and mixed use core to meet the Semi-Rural designations. The Bonsall community's traditional "crossroads" where road, water and wastewater infrastructure, as well as schools, churches, shops and businesses are already in place. We are not interested in changing the Community plan from agricultural, estate lots and an equestrian life style to a high density Village to provide leapfrog development. How is the County going to define Villages in the future based on this project and its requested amendment to the General Plan.
- How many and which Goals and Policies would have to be amended to accommodate this SP/GPA? This is the question. We are arguing that the SP/GPA requires such broad and fundamental changes to the County General Plan that the project cannot be accommodated without scrapping the County's core Vision.

Second, the project design itself defies the GP principles, goals and policies for Village development, or Village expansion, which the Community Development Model reflects.

- The 608-acre project site, only a portion of which is actually owned by the applicant, sprawls 2 miles N-S, and 2 miles E-W across several thousand acres, largely in active agriculture. These surrounding acres are owned by people whose dreams and ambitions for their rural properties are in accord with the Community Development Model's Regional Category assignment: Semi-Rural and Rural.
- The sprawling shape of the site creates some 8 miles of edge effects that will threaten surrounding agriculture, horticulture and animal husbandry that the GP Community Development Model protects by designating this area for Semi-Rural and Rural development.
- With 1746 units and 90,000 SF of commercial on 608-acres, there is insufficient land available for "feathering" residential densities as the Community Development Model intends and describes.

Please clarify and answer the above statements as they are questions regarding the project and the GP conflicts?

The site requires 3 separate commercial nodes to support the "walk-able" claim. It is a stretch to characterize the project as a "walk-able Village" when it is, in fact three circles of dense housing, two of them are at least a mile from the what the Community Development Model

- How does this project characterize as development Village amenities not as LEED does. The LEED standard for "walking distance" is ½ mile, the GP also cites ½ mile (GP, p.3-8). Why Is this project allowed to change what LEED stands for and our General Plan's Village and "Smart Growth" definition?
- This is not the "walk-able" compact Village it pretends to be. Why is the project allowed to state that it is?





Dedicated to enhancing and preserving a rural lifestyle



Chapter 1 of the General Plan contains an Introduction and Overview with some direct statements, such as:

P 1-4

The General Plan must be referred to in its entirety, including separately bound portions (such as community plans). While the GP is internally consistent, some issues are addressed through multiple policies and some receive refined and more detailed direction in Community Plans.

P 1-5

Policies cannot be applied independently

If you are a SD County resident or property owner, the GP indicates the general types of uses that are permitted around your home and changes that may affect your neighborhood, and the policies the County will use to evaluate development applications that might affect you or your neighbors. The Plan also informs you regarding how the County plans to improve mobility infrastructure, continue to provide adequate parks, schools, police, fire, and other public services, protect valued open spaces and environmental resources, and ...

How does this project meet or somehow become consistent with the General Plan with so many goals and policies being ignored in the General Plan? <u>Please don't insult me with the "it will once it is approved."</u>

The essence of the General Plan lies in its goals, policies, and implementation programs how does this project meet the goals, policies and programs?

ARCHAEOLOGICAL RESOURCES

2.6.5.1 Archaeological Resources M-CR-1:

Prior to approval of a Final Map, the applicant shall implement the data recovery program prepared by Mary Robbins-Wade (Affinis 2013) for site CASDI-20436. The data recovery program shall be implemented prior to the commencement of any grading and/or improvements. All data recovery shall include a Luiseño Native American monitor. Have the tribes commented and selected the Native American monitor?

Under 2.6.1.4 Records Search Results:

CA-SDI-4808 was originally recorded during the archaeological survey for the proposed I-15. It was described as a "small milling site, which may be considered a branch of CASDI-4807. CA-SDI-4808 was tested in 1978 to determine site boundaries and evaluate significance. The report concluded that the assemblage appears to be much too limited to make a case for any type of site, which would be distinct from the two villages during San Luis Rey II times. The previous survey concluded that no hypothesis can be made at this time regarding its function during a possible earlier occupation."

The 1978 study is out of date why has a more recent study been properly and thoroughly conducted?





Dedicated to enhancing and preserving a rural lifestyle If review of the justification by the local tribes shows the study to be inadequate, will required?



After talking with several representatives of both the local Indian tribes and the Director of the Native American Heritage Commission in Sacramento several sites have not be identified by this developer and a discussion has be ongoing and will continue either prior to submittal to the Planning Commission or after their possible approval. Statements by them should be of great concern to the developer and the County. *This was written in statement form but interest is in how is this issue being handled?*

2.6.1.4 Records Search Results

The TR and DEIR propose to use studies that are nearly 35 years old. They need to be re-examined by today's standards and in the light of additional information?

BIOLOGICAL RESOURCES

2.5.1.2 Vegetation Communities

The Biological Resources Report [the Report] identifies three sensitive plant species present on-site: Engelmann oak, prostrate spineflower, and southwestern spiny rush. All three are on the County's List D of sensitive plant species and all three are reported as relatively small numbers of individuals. *Do listed plants have to be represented on-site in large numbers to gain significance?*

Is there quantitative data available to know whether the population sizes found on-site are significant within the region?

If not, how is it determined that a local population is insignificant?

Aren't rare, threatened or species of concern logically less numerous in most plant formations?

2.5.2 Analysis of Project Impacts and Determination of Significance 2.5.2.1 – Special Status Species

The Biological Resources Report [the Report] of the DEIR lists 13 federal/state species of special concern or Group 1 species of animals that would be impacted by the development of the Lilac Hills Ranch project [the Project] ranging from orange-throated whiptail lizards to southern mule deer. Reptiles and small mammals are judged to be at greatest risk for direct impact because they move more slowly and likely would suffer greater losses during construction activities, while larger mammals and birds are more mobile and could possibly escape to somewhere else more easily. Is the DEIR saying that reptiles, amphibians and small mammals would likely be sacrificed for this Project given their relative immobility?

What are the population densities of amphibians, reptiles and small mammals that are likely to be extirpated by construction operations?

To where would birds and larger mammals be dispersed?

What are the territorial ramifications and chances of survival for these displaced species?





Dedicated to enhancing and preserving a rural lifestyle



For some of the anticipated species that were not observed during the directed surveys, e.g. the coastal California gnatcatcher, it appears that the timing of the directed surveys took place during the less than optimum periods of July and August, the extreme end of the season. Although still within the survey guidelines, they were conducted during a very dry year, which minimizes the chance of sighting such species on-site. Since this was within the guidelines but a very dry year would a second survey be conducted on such a large acreage project?

The surveys were also compressed into a two-week period [3 surveys on three consecutive Tuesdays], which minimizes the chance of observing the gnatcatchers. Why were such directed surveys conducted so late during a dry year? Why were the surveys scheduled in such a compressed time period at the end of the season?

While reviewing the Attachment 1, Post-Survey Notification of Focused Surveys for Least Bell's Vireo [LBV] for the I-15/395 Master-Planned Community MPA, it was noticed that Figures 1, 2, & 3 indicate a much reduced Project area and boundary for the least Bell's vireo survey than is expected for the present Project. This seems to indicate that the survey was completed on a Project site that significantly differs from the present Project. *How can the cited survey be appropriate and complete for the present Project?*

The addition of considerable acreage since the May, June, & July 2011 LBV surveys means that the additional areas were not properly or adequately surveyed for least Bell's vireo. Will the applicant resurvey these new areas included in the present Project during the appropriate breeding season? The wetlands that are appropriate habitat for this species extend into the subsequently acquired acreage not represented on the submitted map.

Further, the Project boundaries shown to include the survey areas mapped in the Biological Resources Report for the coastal California gnatcatcher do not match the present Project boundaries. The survey maps [Figures 1, 2, & 3 of Attachment 2, Post-survey Notification of Focused Survey for Coastal California Gnatcatcher, I-15/395 Master Planned Community MPA] indicate a much reduced Project area and boundary for the gnatcatcher survey than is expected for the present Project. This seems to indicate that the survey was completed on a Project site that significantly differs from the present Project. *How can the cited survey be appropriate and complete for the present Project?*

The addition of considerable acreage since the July/August 2011 gnatcatcher surveys means that the additional areas were not properly or adequately surveyed for gnatcatchers. *Will the applicant re-survey these new areas included in the present Project?*

The Report suggests that although these anticipated species, and others not listed in the Report, would be impacted by habitat loss caused by grading, construction, and human occupation, it finds that the impacts would be:

"...less than significant given the wide ranges of the species and the fact that the project does not contain a regionally significant population of these species." How can that be possible to arrive at this conclusion?





Dedicated to enhancing and preserving a rural lifestyle



The analysis fails to:

- 1. Demonstrate with data or suggest what a regionally significant population for any of the cited species is:
- 2. Does not estimate the on-site population density of any of the cited species to allow a comparison of the site to the region;
- 3. And, does not explain how the scope of a species' range can exempt the loss of a local population. The loss of local populations or portions of local populations within a species' range does not affect the notional range of the species necessarily, but does have significance in reducing the regional population of a species within the range boundaries.

Do the ranges they refer to include urban as well as undeveloped areas, agricultural as well as natural areas, and what is their extent and density?

Within cismontane San Diego County, most habitats and wildlife populations have a mosaic distribution as a result of human occupation and transportation corridors. To what extent has the historical range of any of these species already been diminished, making even small, local populations, like those on-site, significant?

On what basis was the determination made that on-site populations of the 13 species were not consistent with other significant local or regional populations?

Given the mosaic distribution of those 13 species within the county and southern California, how does the Report distinguish the Project's on-site populations as being insignificant compared to other off-site populations that may be deemed significant?

There was no data presented that showed any quantitative or qualitative measure of the significance of the on-site population sizes of the 13 species, or their relationship or linkage to nearby off-site populations. WHY? The fact of their presence suggests that there is some significance. With the paucity of data presented can we reasonably conclude that 'on-site populations' are not a significant part of a larger regional population?

The edge effect impacts noted by the DEIR (i.e., noise, lighting, invasive plants, grading encroachments, proximal human presence, etc.) to these 13 sensitive species are stated to:

"...be less than significant considering the number of individuals of each species to remain after implementation of the project would be low."

However, since the Report has not quantified:

- 1. The existing on-site population densities;
- 2. The population density thresholds that are deemed significant;
- 3. Or, the expected on-site population densities after construction of the Project, How can the Report establish that the impacts are "less than significant?"

Are there data that have not been reported?





Dedicated to enhancing and preserving a rural lifestyle



Should not the Report have presented an objective basis for the threshold of significance?

The Project would directly impact eucalyptus woodland, orchards, and oak woodlands. This would result in the direct loss of functional nesting habitat for raptors. The Project could also indirectly impact nesting raptors that remain on-site or adjacent to the Project through edge effects, such as close human occupation, noise and lighting why was this information not included in the report?

Further, construction operations, blasting for years also have the potential to disrupt nesting and breeding among raptors. Raptors are protected, as a group, by California Fish and Wildlife codes. The DEIR suggests that this disruption could be mitigated by scheduling construction outside of raptor breeding season, implementing some sort of noise attenuation measures or conducting surveys to impose construction avoidance measures. *How is this to be achieved?*

Would the applicant, or the County, seriously consider limiting construction to the August to December portion of the year? What are the limits of effectiveness of the hinted at attenuation measures? And, since phase one of the Project surrounds the principle open space and raptor nesting corridor being proposed for the Project, would the applicant actually limit construction near that nesting area? Or, would the applicant mitigate the mitigation by trying to survey the potential impact out of existence?

The DEIR asks the reader to "Refer to Table 1-3, Project Design Considerations, in subchapter 1.2.2 for more details" about preconstruction nesting raptor surveys and complete avoidance measures. The Table of Contents directs the reader to "Table 1-3, Summary of Additional Project Design Considerations, page 1-34," however, the table is missing from that page and every other page in section 1.2. Is this information available somewhere else? And, if so, where?

Does this missing table information address the effects on nesting raptors from blasting?

Will the blasting component of the grading be timed to avoid nesting periods of raptors?

Blasting activities are likely to have a much more dramatic affect on nesting birds at a much greater distance than the apparently less significant rumbling of bulldozers and earthmovers. Despite a lack of data to inform the public on the decibel contours that raptors find irritating enough to preclude breeding, the DEIR reaches the conclusion that, "raptor nesting impacts would be less than significant. This is incongruent with the information presented. How is this done?

The DEIR addresses raptor foraging areas saying,

"Almost all of the on-site habitats are suitable for raptor foraging. The project would directly impact 538.29 acres of the 610.76-acre site [reportedly, it is 608-acres], which is 88% of the raptor foraging habitat on-site. This would result in the direct loss of foraging habitat for raptors. The project could also indirectly impact foraging habitat that remains on-site or adjacent to the project through edge effects..." [underline added]





Dedicated to enhancing and preserving a rural lifestyle

The DEIR goes on to say that the impact of the Project to the raptor foraging area is more than 5% of the foraging habitat on-site. And yet, this declared significant impact to 538-acres of forage area would be mitigated by phasing the purchase or designation on-site of mitigation acreage based only on the native vegetation lost to the Project [about 81-acres or 15% of the total], not the agricultural lands to be sacrificed to the Project. *How is this possible?*

As the DEIR says, raptors make significant, and productive use of the orchards, vineyards and row crops present on the Project site for foraging. Why would the applicants not have to mitigate the loss of forage area represented by the agricultural lands on-site as well?

Is the applicant saying that raptors, with 608-acres on which to forage, can 'get by' with a small percentage of the present foraging acreage at a new mitigation site?

Will the edge effects caused by the presence of the Project on-site (i.e., noise, lighting, proximal human presence, dogs, cats, etc.) render any attempted on-site mitigation of foraging area loss within the planned 102-acres of open space less than significant?

The DEIR says such edge effects may compromise on-site mitigation. And if that is true, how will such effects be monitored and mitigated?

And, do these types of edge effects render the planned designated open spaces ineffective for the purposes they are being set aside?

The on-site restoration of wetlands may be seen as possible and acceptable mitigation by the applicant and the county, but since the entire 608-acres has been functioning as raptor foraging area heretofore, the idea that any of the 608-acre Project site could be used to mitigate the loss of that same foraging area is an exercise in double-counting will that be done?

Table 1-2 in Chapter one of the DEIR shows the grading quantities by phase to be cut and filled. According to this table, the first two phases will have deficits of fill compared to the amount to be cut in each those phases. Since the applicant claims that the 4-Million cubic yards of earth to be moved on the Project site will not require import or export to or from the site, borrowing from future phases will be necessary. Will the applicant adjust the timing and purchase of mitigation acreage to accommodate the borrowing of fill from future phases that will prematurely impact raptor foraging during the earlier phases?

Will that grading activity in future phases adversely affect raptor nesting in the earlier phases as well as the future phase that is to make up the fill deficit?

Black-tailed jackrabbits were observed on-site. While a 'species of concern', the DEIR suggests that the impact to this species is less than significant, largely because it is judged [without data] to have a less than significant local population. Finding a black-tailed jackrabbit anywhere in northern San Diego County is becoming exceedingly rare. To suggest insignificance for this species, the authors of the DEIR should cite census data showing that the individuals observed on the Project site are not the last remaining members of the species in the north county region. It is possible that the population on the Project site is the last within the region. *How can this be justified as less than significant?*





Dedicated to enhancing and preserving a rural lifestyle



It is noted that the Project will be pumping ground water from existing wells on-site. Since the open space riparian woodlands that run nearly the length of the Project and transect it at several points are dependent on adequate ground water to support the oaks, willows and other riparian species, how will the applicant manage the long term ground water levels in the open spaces? How will the drawdown of the projects wells impact other agricultural wells in the area? Where is the study?

The applicant is proposing to hand off those riparian open spaces to another agency of some sort [still unnamed]. Will that eventual agency share responsibility and authority over the wells that will have a direct impact on the ground water availability for the riparian habitats?

In the event of a drought, will the managing agency be able to restrict ground water pumping for the benefit of the open spaces?

What will be the mechanism of implementing such a restriction?

Will the managing agency have priority on ground water for irrigation to benefit the created and restored wetlands being offered as mitigation for the destruction of other wetland areas after the five-year establishment period?

2.5.2.2 – Issue 2: Riparian Habitat or Sensitive Natural Community [M-Bio-2]

The DEIR's analysis of the impacts to riparian habitat or sensitive natural communities concludes that there will be significant impact and recommends that a Resource Management Plan [RMP] be prepared before the issuance of grading permits.

Are there unknown factors that prevent the RMP from being prepared for release along with the DEIR and related documents beyond a conceptual treatment? So much of what is presented in the Specific Plan for this Project is conceptual or a possible, but undeclared, choice among several alternatives that it is difficult to consider a conceptual RMP as anything more than a suggestion.

The wetland restoration and development areas [= open spaces] are biologically surveyed and mapped. *Why is the plan not already developed?*

The DEIR is to relate meaningful, specific information in a way that the public can understand and to which it can respond. Delaying the development of the RMP until after Project approval hides the resolution of a significant impact from the public until there is much less, if any, chance of commenting meaningfully why is this delay acceptable to the County?

Further, the DEIR is not clear on what entity will own and manage the proposed open space easements on which important habitat creation or restoration will take place, suggesting the possibility of a private conservancy, the County, or some other experienced entity. *Which is it?*





Dedicated to enhancing and preserving a rural lifestyle



How will these easements be financed into the future? The DEIR is indefinite about endowments or Community Facility District formation or some other finance mechanism.

How will the applicant ensure the financial stability of the open space easements in perpetuity without burdening County taxpayers?

JURISDICTIONAL WATERS AND WATERWAYS [M-BIO-3 and M-BIO-4]

The DEIR identifies significant impacts to jurisdictional waters caused by the Project and proposes to mitigate that loss with restoration of degraded wetlands and creation of new wetlands adjacent to the existing wetlands on-site in open space areas.

The re-vegetation plan presented as M-BIO-4 is not clear regarding its success criteria. That plan requires 80% transplant/container plant survival in year 1. Is the allowance of 20% plant failure in year 1 made up in year 2 with replanting?

Is the required native plant cover percentage in year 2 based on percentage of total plant cover, including non-native species? Or, is it a requirement that 50% of the total surface area must be covered with native species?

Similarly, is the 50% diversity requirement in year 2, diversity of native species versus non-native species? Perhaps a better question is how does one arrive at a percentage of diversity?

And, what is the meaning of the density percentage compared to the cover percentage?

What is the proposed methodology for determining these parameters? Quadrats? Transects? Estimation? The Biological Resources Report is uncertain which would be employed.

Shouldn't this plan be presented in a more complete and understandable form?


The Report acknowledges that the open space areas within the Project would be largely confined to the drainage courses that the Project will avoid [Biological Resources Report 3.2.8, p. 81]. The Report describes the open space areas as "...narrow and mostly surrounded by development except along the western and southern boundary of the project." The Report also suggests that significant edge effect impacts on the proposed open space areas of the Project would result from increased human access, potential increases in predation/competition on native wildlife from domestic animals, potential increases in invasive plant species or other domestic pests, alterations to natural drainage patterns, potential noise effects and potential effects on wildlife species due to increases in night time lighting. These significant impacts would most affect sensitive riparian birds, but, the DEIR says,

'habitat quality, functions and values would likely decrease also."





Dedicated to enhancing and preserving a rural lifestyle



Surprisingly, the Report asserts, that these significant edge effects can be mitigated by a 50-foot buffer around the preserved wetlands in the on-site biological open spaces. A 50-foot buffer poses little challenge to domestic animals, children or adults, night lighting, invasive plant species or other domestic pests. Adding fencing and signage is only marginally helpful. How will the applicant ensure the integrity of the preserved wetlands and open space in the face of these significant impacts?

How will the mitigation of these impacts be monitored and adequately enforced?

Why is there no definitive plan described in the DEIR that addresses how these preserved wetlands will be secure from the reported threats?

What was the basis for dismissing the significant impacts by simply adopting a 50-foot buffer?

There will be trails within the limited building zone [LBZ]. How will the LBZ address the edge effects cited?

2.5.5.3 Wildlife Movement and Nursery Sites

The DEIR says that the impacts to wildlife movement and wildlife nursery sites would be less than significant and no mitigation is required. However, riparian woodland and wetland corridors are the conduits for movement of many animal species. The principal drainage for the Project and its surrounding area runs along the western edge of the Project site with multiple tributary drainages running through the Project in southwesterly directions toward the principal drainage. This drainage system, and its associated wetlands and riparian woodlands, offers transit corridors for the animals inhabiting the Project site as well as neighboring properties.

However, the Project is proposing culvert pipes under the roads that transect the wetland corridors that will range from 18-inches to 54-inches in diameter. Six of the seven wetland crossings are proposed to have culverts of 18- to 30-inches diameter. These culverts are too small to allow effective transit by wildlife and will impose barriers to movement. To be effective transit elements under the roads crossing the wetlands and to encourage wildlife to avoid crossing the surface of the roads, such culverts should be a minimum of 54-inches to accommodate larger mammals. What is the basis for proposing smaller pipes? Bridging should be considered for several of the crossings why was this not included in the plan?

While these corridors have not been 'designated' in the draft MSCP/PAMA plans for the County, they perform the same function in the area of the Project site as the corridors delineated in the MSCP/PAMA plan, only on a more local, or secondary scale. To say that their destruction is less than significant must depend on whether the on-site and nearby off-site populations can be quantified as significant or not. That has not been done. WHY NOT?



Page 21 - 56



Dedicated to enhancing and preserving a rural lifestyle

However, given the scope of the Project, likely any local value of these drainage wellands as transit corridors will be compromised by the edge effects caused by the Project and the direct impacts caused by road crossings within the Project. What objective assessment has been done to determine the significance of these impacts, if any?

As for nursery sites, of the 13 Group 1 species observed on-site, 6 are reptiles or mammals. The seven bird species would likely nest in the riparian woodland or orchard areas. Why is this not significant?

2.5.5.4 Local Policies, Ordinances, Adopted Plans

The DEIR suggests that the Project would comply with several County, State and Federal policies and laws relating to biological resources. However, the DEIR notes that under the Natural Community Conservation Plan [NCCP] for coastal sage scrub [CSS] vegetation, there is no *de minimis* limit for significance. Yet, there is no data to support the conclusion that the 17-acres of CSS to be removed by the Project is insignificant, even in the face of the California Department of Fish and Wildlife's estimate that in the five county southern California region covered by NCCP, approximately 85 to 90 percent of the historically occurring CSS has been extirpated. The DEIR seems overly casual about designating this 17-acres of CSS as insignificant. And, interestingly, the NCCP plan for San Diego County will be manifested in the still draft MSCP/PAMA.

So, what are the ramifications for mitigation if the draft MSCP/PAMA is not approved?

Will there be a significance threshold established in the MSCP/PAMA for CSS if it is approved?

Doesn't the nibbling away of CSS, even when in small stands, inexorably work against the principles of the NCCP CSS program?

At what acreage does a stand of CSS become significant without a delineated animal species observed on-site?

CUMULATIVE EFFECTS

The Report and DEIR pay little attention to the cumulative effects of the Project on regional biological resources. The Report and DEIR focus on effects within the boundaries of the Project with little acknowledgement of the ramifications of this Project on the County as a whole or the Bonsall and Valley Center Planning Area. The Report cites 8 projects that were compared and evaluated against the proposed Project. The review asserts that the majority of the impacts generated by this collection of historic, current and planned projects were to agricultural lands, with little to no impacts to native upland or riparian habitats.

Of course, the Report makes that statement with some satisfaction, apparently not realizing that the loss of agricultural land is contrary to one of the County's General Plan Guiding Principles, as well. Further, all eight of the referenced properties in Table 7 [p.84] are much smaller than the proposed Project, the largest being 44.2-acres and the smallest 5-acres. All are within a few miles of the proposed Project and all are planning parcels larger than 2-acres, some as large as 4-acres in compliance with the present county General Plan and the Bonsall and Valley Center Community Plan. The proposed Project does not comply with the county's General Plan or the Bonsall Community Plan in this regard.





Dedicated to enhancing and preserving a rural lifestyle
Bonsall has lost 804 acres of agriculture based on the General Plan specific requests appears to be consistent with the "new" goal of developing all agriculture into roof General Plan states it wants to support agriculture would this project even be considered?

The comparison doesn't seem an apt one for analyzing regional cumulative effects. If we take San Diego County as the 'region' or even North San Diego County as the region, we should be looking at the historic extent of coastal sage scrub, southern mixed chaparral, southern coast live oak riparian woodland, coast live oak woodland, southern willow scrub, southern willow riparian woodland, and wetlands within that area compared to what exists today. We should then ask to what extent have these vegetation communities been extirpated and to what extent the remaining examples of those communities have significance. Comparing proposed destruction in one project with destruction that has or will result in a handful of other smaller projects isn't an effective measurement of cumulative effects. Will the county examine meaningful cumulative effects within the entire county or, at least, within the northern part of the county?

The County's Project Alternatives Analysis in Chapter 4 of the Lilac Hills Ranch DEIR is grossly defective in meeting CEQA requirements in five areas that are summarized below:

- 1. The DEIR Objectives against which the Alternatives are judged for Environmental Impacts are biased and should be changed to equitable Objectives, from which compliance against can be fairly measured.
- 2. The Project does not meet its own Objectives, when fairly assessed.
- 3. There is a valid offsite alternate the Downtown Escondido Specific Plan Area (SPA) that needs to be included as an Alternate.
- 4. The Reduced Footprint, Reduced Intensity, and 2.2 C Hybrid are not valid Alternates. These three "Alternates" are density variations of the Project. These Alternates are also not described in enough detail to provide informed Environmental Impact Analysis.
- 5. The Alternates were not fairly assessed in the DEIR by the Applicant.
- 6. When all eight Alternates are fairly assessed, the Downtown Escondido SPA meets more Objectives than the Project or any Alternates.

Overview

The Lilac Hills Ranch Project Alternates from Section 4.0 of are below:

- 1. No Project/No Development Alternative
- 2. No Project / Existing Legal Lot Alternative (49 EDU + no commercial)
- 3. General Plan Consistent Alternative (110 EDU + no commercial)
- 4. Reduced Footprint Alternative (1251 EDU + 6 acres of commercial)
- 5. Reduced Intensity Alternative (881 EDU + 5.6 acres of commercial)
- 6. 2.2C (Hybrid) Alternative (1365 EDU + 15.3 acres of commercial)

There are no issues with the either the selection as an Alternate or analysis performed for the No Project/No Development Alternative, No Project / Existing Legal Lot Alternative, and General Plan Consistent Alternatives. Why is this DEIR so incomplete and when will an alternate be considered such as the Escondido project?





Dedicated to enhancing and preserving a rural lifestyle



INCONSISTENCE WITH GENERAL PLAN & COMMUNITY DEVELOPMENT MODEL

There is a full Environmental Impact for these Alternatives provided by the San Diego County General Plan dated August 3, 2011. All three of these alternatives were in the baseline (or close enough for measurement error) for the General Plan. The relevant Environmental Impact has been disclosed and analyzed in sufficient detail as part of the recent General Plan process.

The Communities of Bonsall and Valley Center support the General Plan Consistent Alternative as the proper land use and zoning for this Project. The 110 unit residential density with A70 zoning is the maximum density land use that the Circulation Element Road Network will support without Direct Development Impact.

1- DEIR Objectives are biased and should be changed WHY WAS THIS ALLOWED?

The legal adequacy of selecting many of the eight Project Objectives does not conform to the requirements of the California Environmental Quality Act (CEQA).

2 - The Project does not meet its own Objectives, when fairly assessed WHY WAS THIS ALLOWED?

Consistency with Objective One – THE PROJECT IS INCONSISTENT WITH OBJECTIVE ONE

The full text of Objective One is below:

"Develop a community within northern San Diego County in close proximity to a major transportation corridor consistent with the County's Community Development Model for a walkable pedestrian-oriented mixed-use community."

The proposed Lilac Hills Ranch Subdivision is a classic urban sprawl development. All of the transportation will be via automobiles, and the existing and proposed Project post-construction road infrastructure does not support the 9 fold increase in traffic and related Direct Development Impact the Project generates to the public road network.

A fundamental premise of Smart Growth is to lower automobile dependency as compared to average Development. The Accretive proposed Lilac Hills Ranch Development does not comply with Smart Growth Principles.

The SANDAG average miles/trip for all of San Diego County is 5.8 miles/trip.

The Accretive Urban Sprawl (AUS) project is proposing an automobile based urban sprawl community that even with exceedingly high internal trip rates is 47% higher than the San Diego County average (8.52/5.8) trip distance.





Dedicated to enhancing and preserving a rural lifestyle



How is the Lilac Hills Ranch project proposed development Smart Growth?

The ONLY mass transit that exists is the North County Transit District (NCTD) Bus Routes 388 and 389. The closest access is at SR 76 and Old Highway 395, a minimum 4 mile trip north from the project site. These routes run eight times a day and mainly link the Pala, Pauma, Rincon and Valley View Casinos to the Escondido Transit Center. If you are going to a regional shopping center or work center, you must take a 30 minute bus ride to the Escondido Transit Center and transfer to another route. The mass transit system only works if you are a Casino patron.

This Project is not consistent with the San Diego County Community Development Model. It is Inconsistent with the Community Development Model which a subset of the San Diego General Plan. Why does the first Objective ignore the balance of the General Plan? Because the Proposed Project is patently inconsistent with the San Diego County General Plan, as well as the Community Development Model within the General Plan.

Consistency with Objective Two – THE PROJECT IS INCONSISTENT WITH OBJECTIVE TWO

The full text with comment areas is below:

"Provide a range of housing and lifestyle opportunities in a manner that encourages walking and riding bikes, and that provides public services and facilities that are accessible to residents of both the community and the surrounding area."

"in a manner that encourages walking and riding bikes" - With 10 Exceptions to Road Standards, the Covey Lane/West Lilac and Mountain Ridge/Circle R intersections, and the traffic load the Project will throw on internal and external roads, who will take the risk of walking or riding a bike?

"public services and facilities that are accessible to residents of both the community and the surrounding area" – There are two issues with this statement.

The first issue: what are the public services and facilities in this Project? A vague statement about a K-8 school site without any commitment to financing or endorsement by the School District, a vague description of the minimum acreage of Parks the County requires? Does the undefined Commercial content include a Supermarket or community market? A restaurant of any kind? A retail gasoline service station?

The second issue: "accessible to residents of both the community and the surrounding area" – Accretive's Traffic Impact Study does not show an influx of non-residents to the area. Is this because the Applicant is overly optimistically portraying the true Traffic Impact and related Direct Development impact of this Project?

Consistency with Objective Three – THE PROJECT AND ALL ALTERNATIVES INCLUDING THE OFF-SITE ALTERNATIVE ARE EQUALLY INCONSISTENT WITH OBJECTIVE THREE





Dedicated to enhancing and preserving a rural lifestyle
The full text is below:



"Provide a variety of recreational opportunities including parks for active and passive activities, and trails available to the public that connect the residential neighborhoods to the town and neighborhood centers."

All Alternates are required to have a Discretionary Permit approved (including a Map approval for the General Plan Compliant Alternative) that must comply with this Objective.

Consistency with Objective Four – THE PROJECT IS INCONSISTENT WITH OBJECTIVE FOUR

"Integrate major physical features into the project design, including major drainages, and woodlands creating a hydrologically sensitive community in order to reduce urban runoff."

There are three issues with this Objective. The first issue is that the Objective is **so vague and subjective that compliance is not measurable.**

The second issue is with the statement: "Integrate major physical features into the project design, including major drainages, and woodlands"

How is taking 608 acres of Rural Land primarily involved in Agriculture, disturbing 440 acres, and creating large areas of impermeable surfaces consistent with this Objective? The Project includes 83 acres of road surface and 68 acres of manufactured slopes. Is it desirable to increase storm water runoff volume and velocity with impermeable surfaces? Does introduction of large quantities of urban surface water runoff Total Dissolved Solids and Pathogens benefit the woodlands?

The third issue is with the statement that follows: "creating a hydrologically sensitive community in order to reduce urban runoff."

Accretive is proposing disturbing 440 acres of 608 total acres of rural farm land and populating a high percentage of the 440 acres with impermeable surfaces. *Is this what a hydrologically sensitive community is?*

Consistency with Objective Five – THE PROJECT AND ALL ALTERNATIVES INCLUDING THE OFF-SITE ALTERNATIVE ARE CONSISTENT WITH OBJECTIVE FIVE

The full text is below:

"Preserve sensitive natural resources by setting aside land within a planned and integrated preserve area."

Any Project required to have a Discretionary Permit approved (including a Map approval for the General Plan Compliant Alternative) must comply with this Objective.

Consistency with Objective Six – THE PROJECT IS CONSISTENT WITH OBJECTIVE SIX BECAUSE THE OBJECTIVE IS BIASED IN FAVOR OF THE PROJECT EXPLAIN WHY THIS OBJECTIVE IS CONSISTENT?





Dedicated to enhancing and preserving a rural lifestyle The full text with comment areas highlighted is below:



"Accommodate future population growth in San Diego County by providing a range of diverse housing types, including mixed-use and senior housing."

In this Objective, **the County re-brands dense Urban Sprawl as a desired attribute**. The General Plan Alternate does not meet this objective, because it does not have Urban Density mixed use and senior housing.

This Objective is another example of where the County has structured the Objectives of the EIR so narrowly with an intended bias such that only the Lilac Hills Ranch Project as proposed by the Applicant can fulfill the Project Objectives. This approach leads to a self-serving and biased environmental analysis. Why is this acceptable?

<u>Consistency with Objective Seven – THE PROJECT AND ALL ALTERNATIVES INCLUDING THE</u> OFF-SITE ALTERNATIVE ARE CONSISTENT WITH OBJECTIVE SEVEN

The full text is below:

"Provide the opportunity for residents to increase the recycling of waste."

Having an on-site recycling facility is not the sole opportunity to increase recycling of waste. The huge amounts of waste the Accretive Urban Sprawl (AUS) requires creation of a recycling center to reduce trash truck route miles such that the project perhaps marginally complies with Traffic Level of Service on trash day.

All of the Alternatives comply with this Objective equally.

Objective Eight - THE PROJECT AND MOST ALTERNATIVES INCLUDING THE OFF-SITE ALTERNATIVE ARE CONSISTENT WITH OBJECTIVE EIGHT

The full text is below:

"Provide a broad range of educational, recreational, and social uses and economically viable commercial opportunities within a walkable distance from the residential uses."

Developing the Project at General Plan densities and preserving agriculture and residential based businesses (such as the existing Accretive Agricultural Operations Office located on 32444 Birdsong Drive) on the same or nearby Parcels achieves this Objective **perhaps better than the Proposed 1746 EDU Accretive Urban Sprawl Project.**

3 - A valid offsite alternate – the Downtown Escondido Specific Plan Area (SPA) has been deficiently ignored.

There exists a reasonable off-site CEQA compliant Alternative to this Project – the 1746 EDU and 90,000 sq. ft. mixed use Escondido Downtown Specific Plan Area (SPA) Project.





Dedicated to enhancing and preserving a rural lifestyle

The City of Escondido **SINCE 2007** has been developing an infill redevelopment mixed use Downtown Specific Plan Area (SPA) less than 14 miles south from the proposed Lilac Hill Ranch project. The Escondido Downtown SPA has a (City of Escondo) General Plan build-out Equivalent Dwelling Unit increase (EDU) of 5,275 EDU plus additional mixed use commercial uses.

Unlike the Accretive Project, the Downtown 1746 EDU Escondido Equivalent Project **meets Smart Growth** and LEED-ND location requirements, because it is an infill development with requisite infrastructure truly within walking distance of the Escondido Transit Center which has access to the Sprinter Train as well as being a hub for North County and Metropolitan Bus lines. Additionally, this location is less than a mile from access to I-15.

The project has existing medical, school, fire, police, and most importantly, Circulation Element Roads and mass transit. The Air Quality and Greenhouse Gas impacts of siting the project in Downtown Escondido are orders of magnitude less than the proposed project site in rural greenfield agricultural lands.

The impact on Biology, Agriculture, and Community are non-existent. The Escondido Downtown SPA supports a project of equivalent size to the proposed Accretive Lilac Hills Ranch project and is consistent with both the City of Escondido General Plan and the County of San Diego General Plan.

The Downtown Escondido SPA also provides a more viable solution for senior living facilities, including Assisted Living, because it is within two miles from the two Palomar Hospitals and major medical facilities.

The Downtown Escondido SPA document is available at the following link. http://www.escondido.org/Data/Sites/1/media/pdfs/Planning/DowntownSpecificPlan.pdf

Please also compare the Escondido Downtown SPA level of specificity and completeness of design to that of the Accretive Lilac Hills Ranch Specific Plan. The *interim* Escondido Downtown SPA is more complete than the Accretive Lilac Hills Ranch Specific Plan.

The EIR for this project cannot exclude the Downtown Escondido SPA Alternate and comply with the California Environmental Quality Act.

4 - The Reduced Footprint, Reduced Intensity, and 2.2 C Hybrid are not valid Alternates

These three "Alternates" are density variations of the Project. These Alternates are also not described in enough detail to provide informed Environmental Impact Analysis. Table 1 below displays all of the information provided in the DEIR with the exception of a one page map for each Alternate:





Dedicated to enhancing and preserving a rural lifestyle



	Table 1 -Scant Attributes of 3 Alternates Provided							ed		
				Redu	ced		Redu	ced		
	Project		Footprint			Intensity		2.2 C (Hybrid)		
	Gross	Units/		Gross	Units/		Gross	Units/	Gross	Units/Sq.
Land Use	Acreage	Sq. Ft.		Acreage	Sq. Ft.		Acreage	Sq. Ft.	Acreage	Ft.
Single Family Detached	158.8	903		142.1	783		275.5	881	177.0	792
Single Family Senior	75.9	468		71.1	468		0		75.9	468
Single Family Attached	7.9	164		0			0		4.3	105
Commercial/Mixed Use	15.3	211		6.0			5.6		15.3	
Water Reclamation	2.4			2.4			2.4		2.4	
RF/Trailhead	0.6			0			0.6		0.6	
Detention Basin	9.4			5.4			5.5		5.5	
School Site	12.0			9.0			0		12.0	
Private Recreation	2.0			0			0		2.0	
Group Residential/Care	6.5			0			0		6.5	
Institutional	10.7			10.7			10.7		10.7	
Park - HOA	11.8			10.0			3.0		11.8	
Park - Dedicated to County	12.0			6.0			9.0		12.0	
Biological Open Space	103.6			168.8			102.7		103.6	
Non-circulating Road	45.7			45.7			41.5		43.1	
Circulating Road	37.6			37.6			21.5		30.0	
Common Areas/Agriculture	20.2			20.2			65.0		45.0	
Manufactured Slopes	67.5			67.5			65.0		50.0	
Other/Accretive Math Error*	8.1			5.5			0		0.3	
Total	608.0	1746		608.0	1251		608.0	881	608.0	1365
		* Table 4-1 from DEIR Chapter 4 Project Alternatives has the						as the		
sq. ft. = Square Feet					indica	te	d arithma	atic erro	rs	
HOA = Homeowner's Association										

The major observation from independent experts is that these three Alternate are linear scaled variants of the project with inadequate detail to assess Environment Impact.

Why are these Alternates described so inadequately or not at all? The Applicant's information has multiple math errors (refer to Attachment B – Table 4-1 from DEIR Chapter 4 Project Alternatives). The only other information provided is a one page Map that in two Alternatives did not even perform lot allocation (Attachment C- Reduced Footprint Map and Attachment D- Reduced Intensity Map).





Dedicated to enhancing and preserving a rural lifestyle

This is a deficient level of detail to assess Environmental Impact. Where in any of the text is the definition of Commercial uses and zoning? Despite the naïve arm waving in DEIR Chapter 4, traffic impacts are not linear mathematical relationships. And the list of similar issues to Traffic is very long. The proposed request for the 10 road modifications is not legally defendable by the County and as a tax payer I want to know why this is even considered?

In the interest of brevity, this is inadequate information to make an informed Environmental decision.

5 - The Alternates were not fairly assessed in the DEIR by the Applicant.

Table 2 below rates scoring of Alternates *against the Applicant's biased eight Objectives*. The rationale for assessing the Project is contained in Item 2. The three variant Alternates are scored the same as the Project, except for the 2.2C Hybrid Alternate. The 2.2 C Hybrid Alternate includes Senior Housing, so it scores one Objective higher than the other two.

TA	ABLE 2 - CC	OMPARISON	N TO PROJEC	T OBJECTIV	ES				
		Alternates							
Objectives	Project	Downtown Escondido SPA	No Project/No Development	No Project/Legal Lot	General Plan Consistent		Reduced Intensity	1	
1 -Develop a community within northern San Diego County in close proximity to a major transportation corridor consistent with the County's Community Development Model for a walkable pedestrian-oriented mixed-use community	No	Yes	No	No	No	No	No	No	
2 - Provide a range of housing and lifestyle opportunities in a manner that encourages walking and riding bikes, and that provides public services and facilities that are accessible to residents of both the community and the surrounding area	No	Yes	No	No	No	No	No	No	
3 - Provide a variety of recreational opportunities including parks for active and passive activities, and trails available to the public that connect the residential neighborhoods to the town and neighborhood centers	Yes	Yes	No	No	Yes	Yes	Yes	Yes	
4 - Integrate major physical features into the project design, including major drainages, and woodlands creating a hydrologically sensitive community in order to reduce urban runoff	No	Yes	No	No	No	No	No	No	
5 - Preserve sensitive natural resources by setting aside land within a planned and integrated preserve area	Yes	N/A	No	No	Yes	Yes	Yes	Yes	
6 - Accommodate future population growth in San Diego County by providing a range of diverse housing types, including mixed-use and senior housing	Yes	Yes	No	No	No	No	No	Yes	
7 - Provide the opportunity for residents to increase the recycling of waste	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	
8 - Provide a broad range of educational, recreational, and social uses and economically viable commercial opportunities within a walkable distance from the residential uses	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	
Total Number of Objectives Met	5/8	7/8	2/8	2/8	4/8	4/8	4/8	5/8	





Page 30 - 56

Dedicated to enhancing and preserving a rural lifestyle



Clearly, the least Environmental Impact even to these biased Objectives is the Downtown Escondido SPA Alternate why was this not considered?

Summary and Conclusion

The County's Project Alternatives Analysis in Chapter 4 of the Lilac Hills Ranch DEIR is grossly defective in meeting CEQA requirements.

Objectives 1 and 6 need to be changed to eliminate the bias that the Applicant has intentionally created.

Additional information and studies need to be performed on the Reduced Footprint, Reduced Intensity, and 2.2 C Hybrid Alternates.

The Downtown Escondido SPA Alternate accomplishes the same Objectives as the Project with orders of magnitude less Environmental Impact. This alternate is fully informed in the City of Escondido Downtown SPA Specific Plan and related documents,

Reference A: Escondido Downtown Specific Plan Area http://www.escondido.org/Data/Sites/1/media/pdfs/Planning/DowntownSpecificPlan.pdf

Attachment A: DEIR Project Objective Issues letter dated July 29, 2013

Attachment B – Table 4-1 from DEIR Chapter 4 Project Alternatives

Attachment C – 1251 EDU Reduced Footprint Map

Attachment D – 881 EDU Reduced Intensity Map

Attachment E – 1351 EDU 2.2 C Hybrid Map

City of Escondido May 2012 General Plan

Statement:

If we as lay people and not professional consultants can locate a project of this size that is a LEED ND and deffinetly qualifies as a SMART GROWTH project why was it not mentioned in the EIR and included in the EIR as an alternate?



Page 31-56



Dedicated to enhancing and preserving a rural lifestyle



General Plan (GP) Development Capacity										
	Single Family (Units	Multi- Family (Units)	Retail (Square Feet)	Office (Square Feet)	Industrial / Other (Square Feet)	Open Space, Parks / Misc. (Acres)				
2010 City Area in GP	31,107	16,477	13,001,000	4,091,000	12,389,000	9,000				
2010 County Area in GP	6,450	0	0	0	0	3,500				
2010 City and County Combined	37,557	16,477	13,001,000	4,091,000	12,389,000	12,500				
Build out of City Area in GP	35,350	31,132	32,558,000	24,004,000	20, 102,000	10,500				
Build out of County Area in GP	7,800	0	300,000	0	0	4,500				
Build out City and County Combined	43,150	31,132	32,858,000	24,064,000	20,182,000	15,000				
2035 City Area in GP	32,875	24,133	17,886,000	9,628,000	15,467,000	9,500				
2035 County Area in GP	6,950	0	150,000	0	0	4,000				
2035 City and County Combined	39,825	24,133	18,036,000	9,628,000	15,467,000	13,500				

Total City EDU in 2010 – 47,584

Total City Build out EDU in 2035 – 66,482 Increase of 18,898 from 2010.
-11,886 more than the 54,596 included in the SANDAG 2050 forecast below

SANDAG 2050 GROWTH FORECAST (2030 WAS THE 8/3/11 SAN DIEGO COUNTY GENERAL PLAN BASELINE)





Dedicated to enhancing and preserving a rural lifestyle



Housing Characteristics (2010 Estimates)

Total Housing Units	47,682	100%
Occupied Housing Units	44,973	94%
Vacant	2,709	6%

Preliminary 2050 Regional Growth Forecast

						% Change
	2000	2020	2030	2040	2050	2000-2050
Population	133,559	154,635	165,812	172,490	177,559	29%
Housing	45,050	50,370	52,954	53,738	54,596	19%
Jobs (incl. military)	49,716	66,803	71,331	73,451	74,915	48%

Source: SANDAG www.sandag.org last updated: October 2011

AGRICULTURE RESOURCES

2.4.1.1 Regulatory Framework

DEIR: Subchapter 2.4 Agricultural Resources

- Prime Farmland has the most favorable combination of physical and chemical features, enabling it to
 sustain long-term production of agricultural crops. This land possesses the soil quality, growing season,
 and moisture supply needed to produce sustained high yields. In order to qualify for this classification,
 the land must have produced irrigated crops at some point during the two update cycles prior to Natural
 Resources Conservation Service (NRCS) mapping. The project site does not contain any land
 designated as prime farmland.
- Farmland of Statewide Importance possesses minor shortcomings when compared to Prime Farmland, such as greater slopes and/or less ability to store moisture. In order to qualify for this classification, the land must have produced irrigated crops at some point during the two update cycles prior to NRCS mapping.

Comment: When was the definition of "prime farmland" updated in this area of San Diego County? It is clear that many farm operations are now employing greenhouse and nursery operations which require a much lower amount of irrigation as well as existing on-property soil quality. Imported soil amendments and tents are frequently used. A year-round growing season, characteristic of San Diego County, brings this land much closer to "prime farmland" as compared to farmlands in more inhospitable climates.





Dedicated to enhancing and preserving a rural lifestyle



Comment: In addition, this project will not be built for several-to-many years, particularly in its later phases. The nature of agriculture in America in general and San Diego County in particular will have changed and evolved by that time and so will the classification of the land. The usefulness of all lands in and near the LHR project will have "improved." It would be wise for the developer and those involved in this project to provide a wide-reaching study—regional, State, National & International—to demonstrate how others rate and use their farmlands.

Comment: Does "prime farmland" have a relative definition? The flatness of the mid-west and San Juaquin Valley obviously adds to the number of acres of "prime." So does the drainage aspect of the San Juaquin. However, San Diego County is rolling and hilly, leaving it a poor comparison to US "breadbasket" areas. Where are the detailed report that would redefine "prime farmland" relative to San Diego Count? Please include how other entities--regional, State, National & International—view and define their "prime" farmland?

DEIR: Subchapter 2.4 Agricultural Resources

• Unique Farmland is of lesser quality soils used for the production of the state's leading agricultural crops. Unique Farmland includes areas that do not meet the above stated criteria for Prime Farmland or Farmland of Statewide Importance, but that have been used for the production of specific high economic value crops during the two update cycles prior to the mapping date. It has the special combination of soil quality, location, growing season and moisture supply needed to produce sustained high quality and/or high yields of a specific crop when treated and managed according to current farming methods.

Comments: Under the current trends towards nursery and greenhouse crops, all of the lands in this area would likely qualify as "Unique Farmland." The LHR project could dilute the effect and hamper the production of neighboring farmlands. In addition, since these types of productions are fairly new, it would be unwise and unproductive to consider past use alone, if at all. This area has the potential to continue to grow into a large and thriving industry of locally grown products. Please provide modern and wide-reaching studies—regional, State, National & International--of the characteristics of such operations nationally and internationally as well as the effect of dilution/disruption in urban and suburban proximate areas.

<u>Comment</u>: Rather than rating along the lines of history of having irrigated crops, would not it be more relevant to rate these lands in terms of proximity to other farmlands? Please expand your study to include other agricultural areas, nationally and internationally, and how they rate their multi-use farmlands, particularly in proximity to urban and suburban areas as well as the effect of having farmland uses grouped together vs. atomized.

<u>Comment</u>: Various reports and documents rate Bonsall and Valley Center's agricultural resources as important to the local economy. Please provide a further broad-reaching study depicting the potential disruptive and dampening effect this project will have economically on the Bonsall and VC area and SD County. Please give detailed justification for the likelihood that support of the LHR project contradicts the SD County Board of Supervisor's assertion that Bonsall and VC agriculture is important for the County economy.





Dedicated to enhancing and preserving a rural lifestyle



Comment & Question: It is difficult to know what future agricultural operations could begin in areas that surround this project. Limitations and restrictions of pesticide use could make many agricultural operations more costly or impossible. Considering current and future uphill agricultural battles such as the importation of overseas infestations and foreign competition, the existence of LHR in this area could severely inhibit this area economically? Please include regional, national and international scenarios.

<u>Comment</u>: Are effects of the project considered generally for surrounding areas: immediately, community & regionally? Please provide a study regarding this topic.

DEIR: Subchapter 2.4 Agricultural Resources

The County has completed a contract with American Farmland Trust to help develop the Farming Program. The Farming Program is intended to create the framework for an economically and environmentally sustainable farming industry for San Diego County. The program, when adopted, will include land use policies and programs to keep land available and affordable for farming on a voluntary basis. It will also include economic development tools to help improve farm profitability.

<u>Comment & Question</u>: What is the AFT's evaluation of this project and its effects upon the viability and continuance of this area for profitable farming into the future? Are there implications in this document of the potential effects of the LHR project?

Comment & Question: With a dense residential and multi-use project, restrictions on pesticide use will undoubtedly become more stringent, possibly crippling agriculture in the surrounding area. A detailed study documenting the likely restrictions on pesticide use for surrounding agricultural operations would be wise. As this area has been in agricultural operations for years where is the Phase I and Phase II documentation? How much soil will need to be taken from the site because of the contaminates in the soil? As the document states no soil will leave the site please provide detailed information on how many cubic yards will be removed from the site based on contaminates?

2.4.2.2 Issue 2: Land Use Conflicts

Guidelines for the Determination of Significance

Based on the County of San Diego Guidelines for Determining Significance – Agricultural Resources (County of San Diego 2007c), the project would have a significant impact if it:

Proposes a school, church, day care, or other use that involves a concentration of people at certain times
within one mile of an agricultural operation or land under Contract and as a result of the project, land
use conflicts between the agricultural operation or Contract land and the project would likely occur and
could result in conversion of agricultural resources to a non-agricultural use;

The report later goes on to deem the impact of the proposed LHR school as insignificant: "Because the project design locates the school site away from the project boundary (325 feet), and state regulations prevent aerial pesticide "drift" onto neighboring properties; indirect impacts associated with the proposed school would be **less than significant WHY?**. In addition, the future school site would include fencing and security gates to prevent unauthorized ingress or egress and eliminating associated trespass/vandalism conflicts."





Dedicated to enhancing and preserving a rural lifestyle



Comment: Regulations require schools to be further than 1 mile from agriculture operations. This school site is 325 feet from an existing operation. Avocado & Citrus are vulnerable to known and unknown (future) infestations. Inhibiting the freedom to spray pesticides, herbicides and fungicides could doom their operation or endanger the vulnerable population using the school site. Please provide more detailed studies concerning the proximity of "vulnerable" sites such as schools and agriculture operations from regional to international examples and the effects upon the surrounding agriculture operations and vice versa?

As Bonsall has learned in the last year about agricultural and church/schools clearly agricultural will take the hit and farmers will either need to change how they deal with infestations (spraying) or go out of business. *How will this regulation impact neighboring farms and their operations?*

Group residential or (GR) would include "Group Care" land uses with units for independent living, assisted living, and dementia care. With approximately 200 units within a 6.5-acre site, this land use type would be considered a sensitive receptor. The GR area borders off-site estate residential land uses to the east. The remaining three sides are internal to the project site: biological open space lies to the south; and SFS (age restricted single-family detached) is to the north and west. The nearest active agricultural operation to the GR would be approximately 2,400 feet to the southeast or 2,900 feet to the east. As shown on Figure 2.4-4, neither of these agricultural operations is subject to aerial spraying. Because of the distance between these land uses and the fact that no aerial spraying has historically occurred; **no significant impacts** are anticipated.

<u>Comment</u>: Still, within 1 mile. This would inhibit aerial spraying if a future such agriculture operations were proposed for this area. As requested above, please justify why the County is not requiring LHR to consider possible future uses as well as past?

Hazardous Materials Storage, p. 2.4-20 Would this project create regulations that would include an on-site ban on aerial pesticide spraying, restrictions on the types of fertilizers that could be used, and limitations on the types of equipment and hours of operation of maintenance activities? All pesticide and hazardous materials storage, on- or off-site would be required to comply with the state requirements and the applicable regulations enforced by the County Agriculture Weights and Measures. Notwithstanding storage protection measures and regulatory compliance, significant impacts could occur along the AAs identified above (Impact AG-12).

<u>Comment</u>: The restrictions upon proper cultural practices for grove management would endanger the viability of these LHR on-site agriculture operations. If these operations would cease (i.e. kill or damage the trees) because of these onerous restrictions, wouldn't the usefulness of these zones as barriers for this and other use conflicts be removed?.

Pathogens/Diseases, p. 2.4-20

<u>Comment</u>: The shot-hole borer is currently moving towards San Diego County from the north. It is lethal to citrus trees and has no cure, only careful agriculture cultural practices to prevent and manage its spread. The general public knows little about its spread or prevention. This makes management of these and any potential future pests nearly impossible. Please provide a study which compares its spread to agriculture operations from adjacent urban vs. rural and agriculture areas.





Dedicated to enhancing and preserving a rural lifestyle



Nighttime lighting & Agriculture

<u>Comment & Question</u>: How could future possible agricultural lighting practices be affected by LHR? Please provide studies demonstrating various scenarios: effects of lighting incompatibilities from both directions.

2.4.2.3 Issue 3: Indirect Conversion of Agricultural Resources p. 2.4-23 Cumulative impacts related to farmland conversion could also result from edge effects, including trespassing, pilfering of crops, and damaged farm equipment. The pressure, inconvenience, and increased costs of operating remaining farms in areas converting to other uses may render continued farming infeasible or, at least, heighten the attractiveness of selling other farms for development. *How does the applicant intend to fence the project "edge effects" from humans?*

Comment & Question: The economic engine for this region has great potential, but is fragile. Dilution of actual land uses could further endanger the feasibility of the potency of this engine. Wouldn't it be wiser to encourage other uses that are compatible with agriculture instead of inhibitory ones such as the LHR project? Compatible uses could be: agriculture, breweries and wineries, and other food-processing and production operations, flowers and green house agriculture.

<u>Comment & Question</u>: Considering the importance of agriculture to the entire region, a study of agriculture vitality comparing the saturation of agriculture-compatible vs. agriculture-conflicting actual and potential land uses needs to be undertaken?

GEOLOGY REPORT AND SUPPLEMENTAL GEOLOGY REPORT

The report is preliminary and there are many undocumented fills still to be investigated referenced in this report as 4.3.1.1 as "Artificial Fill and Undocumented (afu).

Excavation Characteristics 5.1.1 describe the need for blasting which cannot be quantified to determine the amount and length of time needed to do removals and ultimately placement of fills. Silicates potentially will be a hazard with regard to AQMD standards. *Where is the study on silicates and the travel of the particulates?*

Slope Stability and Remediation describe cut slopes 6.2.1 and fill (manufactured) slopes 6.2.2 in excess of seventy (70) feet in height. There are no seventy foot high manufactured slopes existing in this community which makes these proposed slopes out of character with the community. As the Fire Department can't respond to slopes of this type how will public safety be considered?

The off-site proposed improvements include but are not limited to the widening of West Lilac roads adjacent the Maxwell Bridge 700 feet, Old Highway 395 between Gopher Canyon and Circle "R" and Covey Lane from the intersection of West Lilac all have had minimal review. Why the minimal review as these roads are essential to the access to the project?

The installation of approximately 2570 feet of forced sewer main will require additional investigation and review once easements are established. *Have the easements been provided to install sewer mains?*





Dedicated to enhancing and preserving a rural lifestyle



HYDROMODIFICATION MANAGEMENT PLAN (HMP)

Detention basins construction prior to, during and post construction need to be clearly described as to how they coordinate with the phasing plan. The grading plans, geology reports and HMP have yet to be subject to plan check oversight and current County grading ordinance WHY? The county grading ordinance limits and restricts the quantity of total area exposed at any one time. County environmental restricts percolation of sewer into disturbed material or placed fills. The plan needs clarification of how the construction phasing would comply with all county standards WHEN WILL THIS BE PROVIDED?

Effects Found Not Significant During Initial Study

3.2.24 The project does not introduce a new village but does negatively impact the existing village of rural agricultural residences. Existing infrastructure would be lost and any new infrastructure would change the entire complexion and burden the "Rural Agricultural Economy" that exist. Any new development would restrict accepted practices of farming further increasing the fiscal impact. This is not a fringe of an existing community which becomes very clear when you review all the impact studies which extend to the eastern and western boundaries of the communities of Bonsall and Valley Center.

Specific Plan & Technical Documents

Implementing Grading Plan Sheet 1-9

The plans are preliminary and the general notes lack clarification ofdetail.i.e.

Item 13 removal of all septic systems. County environmental requires the installation of vertical wells into a leach field to replace any loss to existing leach fields if possible. Not all easements have been secured to allow for the removal of all septic systems which will impact design. *Explain what this means as some of the houses will remain on site and the project will build around them?*

Item 14 The existing Village of agricultural businesses do not have light standards that are associated with high density bedroom communities. *Bonsall has a dark skies ordinance and would like to know how this project will impact our ordinance?*

Item 15 Referencing a TM plan that does not exist where easements have not been vacated, quitclaimed or extinguished is too preliminary an exercise to attempt to determine if the plan will work once it is submitted to the governing agency for plan check approval. Why was this project allowed to proceed with all of the missing items described in this document from Bonsall?

Item 16 Regarding the containment of storm water. There needs to be a phasing plan which more closely describes the phasing tied directly to the hydromodification management plan as it subject to NPDES (National Pollution Discharge Elimination System) and the SWPPP (Storm Water Pollution Protection Plan). *When will this be provided?*

Implementing Preliminary Grading Plan & Implementing Tentative Map (Phase 1) These proposed plans reflect a permutation of an existing rural farm "Village" with high density housing which does not exist anywhere in the community. The plans reflect manufactured slopes from 3' to 70' in height.





Dedicated to enhancing and preserving a rural lifestyle



The county grading ordinance requires landscaped coverage and limits the amount of open grading activity at one time. *How will this phasing be accomplished?*

Letters of permission to grade and easements are still outstanding. *How will plans be modified to accommodate outstanding easements if they are not secured?*

With restrictive grading standards how will "Blue Line" streams and migratory corridors be maintained?

As the geotechnical reports are still incomplete there are no previsions for vernal pools if they are identified. *How will they be preserved?*

ROADS AND TRAFFIC

ROADS. Traffic impacts are significant and the applicant has proposed no acceptable mitigation measures. The applicant's request for ten (10) modifications to the County road standards will actually REDUCE road capacities to sub-standard levels. Accretive Investment Group proposes Village development of a rural area. But the applicant does not propose Village capacity roads that are necessary to accommodate the traffic that will be generated by their Village project. Incongruently, and not disclosed openly in the SP or the DEIR, the applicant proposes ten (10) modifications to the County Road Standards that will reduce capacities of roads that were planned, in the first place, to accommodate Rural and Semi-Rural residential development that GP Principles and the land use designation that reflects them have intended for this area. Please note that the Bonsall Sponsor Group does not support nine of the 10 requested modifications.

One purpose of the General Plan Mobility Element and the County Road Standards is to specify road standards and automobile capacities that are necessary to serve surrounding land uses throughout the County. Land Use and Mobility Elements are tightly coordinated. Village-capacity roads are specified as necessary to serve Village land uses. Presumably decision makers will agree that road capacity standards set by the County GP Element and the County Road Standards are "necessary" standards.

However, Accretive Investment Group proposes to compromise standards that are employed uniformly across the County in order to win for themselves entitlements to urbanize land uses -- without responsibility for urbanizing road capacities. Specifically, they propose to add 20,000 Average Daily Trips to Mobility Element roads, and to pass the real costs of improving these roads on to the taxpayers. Further, they are finagling "consistency" with County planning standards pretty much across the board not by complying with them, but by relaxing them.

For example, their proposal is to *DOWNGRADE* West Lilac Road from its current Class 2.2C to a reduced-capacity Class 2.2F. And then, they further propose that two segments of West Lilac Road and one segment of Old Highway 395, which will operate at unacceptable Levels of Service E and F as a result of their new "Village" be sanctioned as official "exceptions" to the County standard for minimum Level of Service. TIF fees of approximately \$5Million are utterly inadequate to afford the road reconstruction necessary to service this development's traffic. The Valley Center Road widening five years ago cost in excess of \$50 Million. Road improvements in already-urban places are expensive. *Is West Lilac Road available for TIF fees improvement?*





Dedicated to enhancing and preserving a rural lifestyle



In remote places road improvement costs are enough to kill projects. No doubt recognizing this problem, the proponents themselves argue *against* improving roads to capacities that are necessary. They say to do so:

- is too difficult and costly
- will require rights-of-way that may be unobtainable
- will be time consuming to construct
- will be disruptive to off-site property owners
- will face opposition from existing neighbors
- will require condemnation of right-of-way
- will impact biological open space.

Accretive does not have legal right of way to build most of the indicated off-site road improvements. Additionally, in order to meet the County Road Standards, two out of four secondary access intersections (Covey Lane and Mountain Ridge) with public roads will require the use of County prescriptive rights (for continual brush clearance) and eminent domain (to secure land from unwilling property owners). Accretive Investments has filed Sight Distance Analyses on these two intersections that confirm the above assertion.

RESPONSE TIME. The SP/GPA fails to meet 5 minute response time for Fire and Emergency Medical Services The Deer Springs Fire Protection District has commented in writing that none of the proposed options listed in the Specific Plan and Fire Protection Plan are feasible solutions for the District to meet the 5 minute emergency response requirement for Lilac Hills Ranch.

- Comparison of the existing General Plan development of 1,320 ADT's to the proposed 19,428 ADT's shows that the proposed project would generate 14.7 times more traffic than the approved General Plan.
- The recently adopted Mobility Element of the County's General Plan does not include the section of New Road 3 from Highway 395 to West Lilac Road. The deletion of the section of New Road 3 changed the classification of Highway 395 to a four-lane Boulevard with a LOS "D" Capacity = 25,000 ADT and West Lilac Road from Highway 395 to New Road 3 to a Light Collector 2.2C, with intermittent turn-lanes with a LOS "D" Capacity of 13,500 ADT.
- West Lilac Road is the primary access road serving the project. Secondary access to/from
 the project site is proposed to be provided by Covey Lane between West Lilac Ranch Road
 and Mountain Ridge Road extending north from Circle R. Drive to connect to West Lilac
 Ranch Road. Both Covey Lane and Mountain Ridge Road are private roads and do comply
 with the County Design Standards.

Consistency Analysis – The proposed Lilac Hills Ranch (LHR) Project is TOTALLY inconsistent with this policy in the following areas. *The project proposes to downgrade W. Lilac Road between Main Street and the planned Road 3 from the classified 2.2C to 2.2F.* The LHR Project proposes placing an additional automobile load of 20,000 Average Daily Trips on the surrounding roadways more than the adopted General Plan approved uses.

- The LHR Project increases traffic on local Private and Public Roads approximately **15 times** greater than from the traffic generated by the approved General Plan.
- At build out the LHR Project Traffic Load exacerbates cumulative road capacity in the surrounding areas with the numerous unmitigated impacts:





Dedicated to enhancing and preserving a rural lifestyle



Significant Direct Impacts:

- The project would have significant direct impacts to each of the road segments listed below. The mitigation for each impact is also listed, as well as the conclusion as to whether the impact would be mitigated.
- Gopher Canyon Road, between E. Vista Way and I-15 SB: No feasible mitigation. Impact would remain significant and unavoidable.
- E. Vista Way, between Gopher Canyon Road and Osborne Street: No feasible mitigation. Impact would remain significant and unavoidable.
- E. Vista Way, between SR-76 and Gopher Canyon Road: No feasible mitigation. Impact would remain significant and unavoidable.
- West Lilac Road, between Old Highway 395 and Main Street: Impact would be mitigated through improvement of the road segment to Mobility Element Road
- Classification 2.2C, subject to exceptions as approved by the County. <u>Impacts would be reduced to less than significant and the project would have a significant direct impact to each of the roadways listed above.</u> We disagree with Chen applicants consultant.
- Ryan's analysis that states that the direct impact is mitigated to less than significance by addition of traffic lights at these intersections because turn lane are not added at the intersections.

Significant Cumulative Impacts:

- The project would have a significant cumulative impact to each of the roadway segments listed below. The magnitude of the impacts below cannot possibly be mitigated by the small amount of LHR project contribution in TIF fees. The <u>impacts will remain as significant unmitigated</u> impacts.
- Camino Del Rey between Old River Road and West Lilac Road;
- Gopher Canyon Road between E. Vista Way and I-15 SB Ramps;
- E. Vista Way between SR-76 and Gopher Canyon Road;
- E. Vista Way between Gopher Canyon Road and Osborne Street;
- Pankey Road between Pala Mesa Drive and SR-76;
- Lilac Road between Old Castle Road and Anthony Road; and
- Cole Grade Road, between Fruitvale Road and Valley Center Road.

Intersection Impacts:

- The project would have a significant cumulative impact to each of the intersections listed below. The magnitude of the impacts below cannot possibly be mitigated by the nominal of LHR project contribution in TIF fees. The impacts will remain as **significant unmitigated impacts**.
- E. Vista Way/Gopher Canyon Road;
- • SR-76/Old River Road/E. Vista Way;
- • SR-76/Olive Hill Road/Camino Del Rey;
- SR-76/Pankey Road;
- Old Highway 395/West Lilac Road;
- • I-15 SB Ramps/Gopher Canyon Road;
- I-15 NB Ramps/Gopher Canyon Road;
- Old Highway 395/E. Dulin Road;
- Miller Road/Valley Center Road;
- • SR-76/Old Highway 395;
- I-15 SB Ramps/Old Highway 395; and
- I-15 SB Ramps/Old Highway 395.





Dedicated to enhancing and preserving a rural lifestyle



Segments Impacts

- The project would have a significant cumulative impact to each of the segments of the I-15 listed below.
- Between Riverside County Boundary and Old Highway 395;
- Between Old Highway 395 and SR-76;
- Between SR-76 and Old Highway;
- Between Old Highway 395 and Gopher Canyon Road;
- Between Gopher Canyon Road and Deer Springs Road;
- Between Deer Springs Road and Centre City Parkway;
- Between Centre City Parkway and El Norte Parkway; and
- Between El Norte Parkway and SR-78.
- The LHR project proposes doing nothing whatsoever to mitigate its I-15 traffic impacts.

Planning for Compatibility:

• "Plan and site infrastructure for public utilities and public facilities in a manner compatible with community character, minimize visual and environmental impacts, and whenever feasible, locate any facilities and supporting infrastructure outside preserve areas. Require context sensitive Mobility Element road design that is compatible with community character and minimizes visual and environmental impacts; for Mobility Element roads identified in Table M-4, and LOS D or better may not be achieved." Please refer to comments on LU-12.2 Maintenance of Adequate Services – Converting Rural Circulation Element 2.2 E to traffic signal controlled Urban Gridlock Environments is not compatible with General Plan Land Use design for the Adjacent Areas.

General Plan Goals and Policies NOT discussed or analyzed in the DEIR include:

LAND USE ELEMENT

LU-1.4 Village Expansion: "Permit new Village Regional Category designated land uses only where contiguous with an existing or planned Village and where all the following criteria are met: Public facilities and services can support the expansion without a reduction of services to other County residents, and the expansion is consistent with community character, the scale, and the orderly and contiguous growth of a Village area"

Comment-INCONSISTENT: If there was an existing or planned Village in western valley Center, Accretive could try to use this provision, instead of being prohibited by the Leapfrog Development provisions of LU-1.2. However, the only "existing or planned Village" in Valley Center is the Village in the central valley where north and south nodes are separated by a dramatic escarpment and Moosa and Keyes Creeks. This area has existed as a "Village", has been planned for expansion for more than 50 years and was designated a SANDAG Smart Growth Opportunity area with the recent update of the County General Plan. The area is sewered and has received a large grant from the state of California to expand wastewater facilities. Valley Center Road which traverses this area and connects to Escondido and Pauma Valley was improved to Major Road standards only a few years ago in anticipation of expanded development here. The Valley Center Community Planning Group has increased residential densities in this area so that about 25% of the community's growth can be accommodated in the "vibrant, compact Villages" the community has envisioned.





Dedicated to enhancing and preserving a rural lifestyle



This provision is a clear companion to and exemplifies the GP support for intensifying development in existing Village areas and its thrust against leapfrog development -- by emphasizing only expansion of an existing Village. The Project also fails to meet the criteria: Its construction would clearly reduce services to all Valley Center residents outside the development by taking away from the economic viability of the existing two Villages, as well as blocking emergency evacuation ability for current residents. As previously pointed out, its urban pattern is totally out of "character and scale" with Valley Center's vision. Nor does a third Village provide "contiguous growth of a Village area." A new Regional Category Village is prohibited in the area of the Proposed Project. This provision would have to be amended to allow this Project, and the DEIR would have to analyze the environmental effects countywide of such an amendment.

LU-2.3 Development Densities and Lot Sizes: "Assign densities and minimum lot sizes in a manner that is compatible with the character of each unincorporated community."

Comment-INCONSISTENT: This is another demonstration of the interwoven fabric of the GP. Densities and lot sizes reflect community character. Valley Center's community character (once you drop Accretive's fiction that there is no existing community) is primarily rural, exemplifying the Community Development Model at the heart of the GP. Urban densities and lot sizes proposed by this Project are inconsistent with the Semi-Rural land use designations established by the GP and CP for this area.

LU-2.4 Relationship of Land Uses to Community Character: "Ensure that the land uses and densities within any Regional Category or Land Use Designation depicted on the Land Use Map reflect the unique issues, character, and development objectives for a Community Plan area, in addition to the General Plan Guiding Principles."

Comment-INCONSISTENT: This is yet another demonstration of the interwoven fabric of the GP. Requiring projects to comply with the applicable Community Plan is the most effective way to meet the GP Goal LU-2, to maintain the county's rural character. Valley Center's community character (once you drop Accretive's fiction that there is no existing community) is primarily rural, exemplifying the Community Development Model at the heart of the GP. This Project is inconsistent with the Semi-Rural land use designations established by the GP and CP for this area, as well as all the Guiding Principles, as previously pointed out.

LU-5.3 Rural Land Preservation: "Ensure the preservation of existing open space and rural areas (e.g., forested areas, agricultural lands, wildlife habitat and corridors, wetlands, watersheds, and groundwater recharge areas) when permitting development under the Rural and Semi-Rural Land Use Designations." **Comment-INCONSISTENT:** If this Project proposed development consistent with its existing Land Use Designations, it would still be required by this provision to "preserve," not destroy. The proposed project destroys even more open space, agricultural lands, wildlife habitat and corridors, and watersheds than it would be allowed with consistent development, by its urbanized design, density, and size, as previously pointed out. Urban densities and lot sizes proposed by this Project are inconsistent with the Semi-Rural land use designations established by the GP and CP for this area.





Dedicated to enhancing and preserving a rural lifestyle



LU-6.1 - Environmental Sustainability: "Require the protection of intact or sensitive natural resources in support of the long-term sustainability of the natural environment."

Comment-INCONSISTENT

There have been thirteen (13) Group 1 animal 'species of concern' observed on the Accretive project site. They include lizards, snakes, raptors, small mammals, large mammals and passerine birds. Most of the wildlife surveys conducted focused on the proposed open space areas, brushing over the considerable land area devoted to agriculture as being disturbed. Of the 608-acres on the Project site, 504-acres will be graded, cut and filled, for the construction of the Project.

The DEIR acknowledges the significant impact to these 13 species [and presumably to other species numerous enough not to be of concern], and particularly the raptors [white-tailed kite, Cooper's hawk, turkey vulture] and the loss of 504-acres of foraging area [including agricultural areas]. The DEIR dismisses this loss with 81.7-acres of on- and off-site mitigation area [presumably already populated by members of these species with whom the Project's individuals will compete], a substantial differential from the complete 608-acres. Many of the individuals of the 13 species will be killed during construction operations, particularly the smaller, less mobile animals. Others will be forced into new territory. Of the larger animals, they will be forced to compete with others of their species in substantially less area.

So, the Project is not protecting sensitive natural resources except those that it is prohibited from completely destroying [largely, riparian wetlands]. Such practices of building urban density projects in rural and even agricultural areas will ultimately decimate the natural environment.

LU-6.4 Sustainable Subdivision Design: "Require that residential subdivisions be planned to conserve open space and natural resources, protect agricultural operations including grazing, increase fire safety and defensibility, reduce impervious footprints, use sustainable development practices, and when appropriate, provide public amenities. [See applicable community plan for possible relevant policies.]" **Comment-INCONSISTENT:** The Accretive Project instead proposes the minimum required open space, eliminates existing and imperils adjacent agricultural operations, and substantially worsens fire safety and defensibility, as shown by the Deer Springs Fire District comments. Instead of reducing impervious footprints, it proposes 1746 residential units etc., covering 504 of its 608 acres. Trumpeting "sustainable" development practices, it completely ignores the fundamental requirements of LEED ND to have a Smart Location and preserve Agriculture. The public amenities necessary to support their proposed city in the county, parks, schools, sewers, are all couched in "conceptual" terms, with built-in defaults to convert acres to still more additional residences. If, for example, the school or park sites (proposed without school and park amenities) are not accepted, the SP provides for their easy conversion to residential uses. This provision would have to be amended to allow this Project, and the DEIR would have to analyze the environmental effects countywide of such an amendment.

LU-6.6 Integration of Natural Features Into Project Design: "Require incorporation of natural features (including mature oaks, indigenous trees, and rock formations) into proposed development and require avoidance of sensitive environmental resources."

Comment: This requirement is again honored only in its violation by this Project. Over four million cubic yards of grading to destroy natural features and create "manufactured" hills suitable only for urbanized residential construction. This provision would require amendment to approve this project. The DEIR would have to analyze the environmental effects countywide of such an amendment.





Dedicated to enhancing and preserving a rural lifestyle



LU-6.6 Integration of Natural Features into Project Design: "Require incorporation of natural features (including mature oaks, indigenous trees, and rock formations) into proposed development and require avoidance of sensitive environmental resources."

Comment-INCONSISTENT

With the exception of the riparian woodlands/wetlands that must be set aside, the 4 million cubic yards of blasting and grading will obliterate any other natural features of the Project site. Once completed, the Project will resemble any urban center in the county, with little of the natural landscape remaining. Native vegetation habitats will be destroyed and mitigated off-site. Animal populations will be destroyed or shoved to the remaining riparian set-asides or off-site. Avoidance of sensitive environmental resources is minimal; destruction of this area's natural features and mitigation elsewhere are the preferred approaches for this project, obviously inconsistent with Valley Center's objectives.

LU-6.7 Open Space Network: "Require projects with open space to design contiguous open space areas that protect wildlife habitat and corridors; preserve scenic vistas and areas; and connect with existing or planned recreational opportunities."

Comment-INCONSISTENT

This Project has reserved minimal open space along wetlands and riparian areas that are particularly protected by federal, state, and county laws. The continuity of the open space will be broken by multiple road crossings with culverts mostly inadequately sized for safe wildlife passage. Intensity urban development will dominate the presently rural agricultural and natural vistas with rows of dense urban rooftops. The open spaces being set aside are not coordinated with the draft MSCP/PAMA and will <u>not</u> connect with any similar open space uses off-site. While the Project is within the draft MSCP boundary, it is not part of a PAMA.

LU-6.9 Development of Conformance with Topography: "Require development to conform to the natural topography to limit grading; incorporate and not significantly alter the dominant physical characteristics of a site; and to utilize natural drainage and topography in conveying stormwater to the maximum extent possible." **Comment-INCONSISTENT:** Could the writers of the GP and the Board of Supervisors with their approval not make more clear that the destruction of the land proposed by this Project's over four million cubic yards of grading to destroy natural features is prohibited? The Project glorifies, not limits grading. The Project proposes to obliterate, not "not significantly alter," the dominant physical characteristics of the site. This provision would require amendment to approve this project. The DEIR would have to analyze the environmental effects countywide of such an amendment.

LU-9.6 Town Center Uses: "Locate commercial, office, civic, and higher-density residential land uses in the Town Centers of Village or Rural Villages at transportation nodes...."

Comment-INCONSISTENT: As previously pointed out in the comments on the Project's total failure to meet the LEED ND Smart Location Requirement, it is not designed as a Transit Corridor or Route with Adequate Transit Service. It is not a "transportation node." This provision would require amendment to approve this project. The DEIR would have to analyze the environmental effects countywide of such an amendment.





Dedicated to enhancing and preserving a rural lifestyle



LU-09.11 Integration of Natural Features into Villages: "Require the protection and integration of natural features, such as unique topography or streambeds, into Village projects."

Comment-INCONSISTENT: This provision was included in the GP because Valley Center required the developers of the north Village to do exactly that, making the streambed there an open space centerpiece of their design in their cooperative plans for their adjacent projects. Accretive instead proposes to obliterate the natural topography for their entire site, grading over four million cubic yards of genuinely natural features into manufactured hills. This policy would require amendment to approve this project. The DEIR would have to analyze the environmental countywide effects of such an amendment.

LU-10.2 Development- Environmental Resource Relationship: "Require development in Semi-Rural and Rural areas to respect and conserve the unique natural features and rural character, and avoid sensitive or intact environmental resources and hazard areas."

Comment- INCONSISTENT: This Project does not respect nor significantly conserve the unique natural flora and fauna of the site, nor does it conserve the rural character of the site. This Project will destroy a mosaic of natural vegetation habitats that are interspersed among agricultural uses. The current mix of natural habitats, orchards and row crops provides distinctive opportunities for a variety of faunal species [several of them sensitive], benefits the local hydrology by restraining and filtering run-off, and presents a pastoral view-shed that is historically characteristic of north San Diego County. The Project will create severe hydrology issues with the addition of hundreds of acres of impermeable road and rooftop surfaces that will cause excessive run-off. Run-off that would otherwise enter the water table and help to stabilize levels vital to the riparian habitats down-slope, will be impounded and/or dispersed on the surface.

The Project will be composed of dense urban village configurations that are completely at odds with rural and semi-rural areas and the natural habitats and populations they support.

MOBILITY ELEMENT

M-12.9 Environmental and Agricultural Resources: "Site and design specific trail segments to minimize impacts to sensitive environmental resources, ecological system and wildlife linkages and corridors and agricultural lands. Within the MSCP preserves, conform siting and use of trails to County MSCP Plans and MSCP resource management plans."

COMMENT-INCONSISTENT

Presently, the trails proposed for the Project will intrude into the buffer and LBZ areas along side the designated biological open spaces as well as the open spaces themselves. The fences proposed to separate and protect segments of the open spaces from the edge effects created by the Project [human intrusions, domesticated cats and dogs, invasive plant species, etc.] will also create barriers to the movement of wildlife. Instead of treating these biological open spaces as retreats and corridors for the movement of wildlife, the trails proposed would turn them into parks for humans and their pets. This will have an adverse effect on the value of these open spaces for wildlife.





Dedicated to enhancing and preserving a rural lifestyle



CONSERVATION AND OPEN SPACE ELEMENT

GOAL COS-2 Sustainability of the Natural Environment: "Sustainable ecosystems with long-term viability to maintain natural processes, sensitive lands, and sensitive as well as common species, coupled with sustainable growth and development."

COMMENT-INCONSISTENT:

The Project will eliminate 504-acres of mixed native and agricultural lands that provide foraging area for numerous animal species identified in the biological resources report. This represents an incremental loss of habitat and ultimately a loss of local wildlife populations within the county and the Project site. The removal of the project site from the inventory of rural lands to create an urban village will constitute an irreversible loss and opposes the intent of sustainable development. It will likely result in growth inducing pressure on surrounding properties as the rural and natural characteristics of the land disappear.

COS-2.1 Protection, Restoration and Enhancement: "Protect and enhance natural wildlife habitat outside of preserves as development occurs according to the underlying land use designation. Limit the degradation of regionally important Natural habitats within the Semi-Rural and Rural Lands regional categories, as well as within Village lands where appropriate."

COMMENT-INCONSISTENT:

This Project proposes to set a devastating precedent for the intrusion of urban development into rural lands. While the Project site is within the MSCP boundary, it is not a part of a PAMA. The site is presently designated for estate housing and agricultural uses but would be modified to allow urban village densities, which would diminish rural and natural lands within the MSCP area and likely induce similar densities on surrounding properties. Such creeping higher densities within the MSCP would ultimately impact the neighboring PAMA areas through edge effects and compromise value of those native habitats and the intent of the MSCP/PAMA program.

COS- 2.2 Habitat Protection Through Site Design: "Require development to be sited in the least biologically sensitive areas and minimize the loss of natural habitat through site design."

COMMENT- INCONSISTENT

Like GP Goal COS 2.2, the prerequisite of the LEED ND standard also is to place development in smart growth locations, such as urban infill and brown fields or adjacent to urban areas where there Is easy access to infrastructure and job centers. This Project fails to meet those goals and, consequently, it will cause significant destruction of biological assets in an area that should be spared under the criteria for a smart growth location.

COS- 3.1 Wetland Protection: "Require development to preserve existing natural wetland areas and associated transitional riparian and upland buffers and retain opportunities for enhancement."

COMMENT-INCONSISTENT

The project is preserving and restoring the on-site wetlands, habitats that are in shortest supply regionally, but the upland vegetation components will be subjected to severe grading, and fuel modification to accommodate the development. Rather than being enhanced, the upland areas will be shaved of value for both flora and fauna.





Dedicated to enhancing and preserving a rural lifestyle



COS- 3.2 Minimize Impacts of Development: "Require development projects to:

Mitigate any unavoidable losses of wetlands, including its habitat functions and values; Protect wetlands, including vernal pools, from a variety of discharges and activities, such as dredging or adding fill material, exposure to pollutants such as nutrients, hydro modification, land and vegetation clearing, and the introduction of invasive species."

Comment -INCONSISTENT

The Project proposes to mitigate the loss of wetlands caused by new road crossings by restoring or creating wetland on-site adjacent to existing wetlands. The value of mitigating wetland losses on-site is questionable given the edge effects caused by human intrusion, domestic cats and dogs, invasive plant species, trash, etc. that cause mitigation efforts to be diminished. Exacerbating the edge effects is the plan to establish trails within and adjacent to the biological open spaces.

Further, the Project's storm water run-off from the massive acreage of impermeable surfaces to be built is likely to impact the water regime within the biological open spaces. Adding too much or, conversely, removing too much water from the water table can have adverse effects on the survivability of the riparian habitat.

HOUSING ELEMENT

H-1.9 Affordable Housing through General Plan Amendments: "Require developers to provide an affordable housing component when requesting a General Plan amendment for a large-scale residential project when this is legally permissible."

Comment-INCONSISTENT: There appears to be NO discussion anywhere in the SP or DEIR regarding Affordable Housing or Goal H-1 and Policy H-1.9. Perhaps, since there are no firm plans for anything beyond the Phase I 354 homes, the County considers this not to be a "large-scale residential project?" Since the overall Project proposes more than 1746 homes and over 5000 new residents, it appears to be a "large-scale residential project." This provision would require amendment to approve this project. The DEIR would have to analyze the environmental effects countywide of such an amendment. Alternatively, the DEIR should contain some discussion and analysis of why this provision is not applicable or is otherwise satisfied.

H-2.1 Development That Respects Community Character: "Require that development in existing residential neighborhoods be well designed so as not to degrade or detract from the character of surrounding development consistent with the Land Use Element. [See applicable community plan for possible relevant policies.]"

Comment: This is yet another demonstration of the interwoven fabric of the GP. Requiring projects "not to degrade or detract from the character of surrounding development consistent with the Land Use Element" explicitly ties housing back to the bedrock Land Use Element, the Community Development Model, and the LEED ND Smart Location Requirement. Unless you resort to Accretive's fiction that there is no existing community (and by extension, no existing "community character" to the western Valley Center neighborhood) plopping an urban project the size of Del Mar into a rural, predominantly agricultural area designated for Semi-Rural uses, would be in significant contradiction to the "character of surrounding development." Once again the GP requires developers to comply with the applicable Community Plan. That is the most effective way to meet the GP Goal LU-2, to maintain the county's rural character. This Project is inconsistent with the Semi-Rural land use designations established by the GP and CP for this area, as well as all the Guiding Principles, as previously pointed out.





Dedicated to enhancing and preserving a rural lifestyle Page 48 - 56



Community Plan Inconsistencies

A. Community Character Goals

Dedicated to enhancing and preserving a rural lifestyle consistenting of low-density estate type residential, agricultural and equestrian uses.

- Policy 1 "Require development in the community to preserve the rural qualities of the area, minimize traffic congestion, and to not adversely affect the natural environment.
- Policy 2 Maintain the existing rural lifestyle by continuing the existing pattern of residential, equestrian, and agricultural uses within the Bonsall CPA.
- Policy 3 Require development to be sensitive to the topography, physical context and community character of Bonsall.

Comment: The SP and DEIR cannot avoid the clear violation of these provisions by the fiction of merely adopting a new Map. The rural character of the project site, indeed all of the Planning Area in Bonsall and Valley Center, will be destroyed by plopping an urbanized area the size of Del Mar in the middle of an active agricultural area. Destruction of a designated Semi-Rural agricultural area cannot be interpreted to be "preservation." The DEIR must, but does not, explain and analyze the environmental effects of this discrepancy Why?

B. Land Use Goals

- **Policy 1** Require subdivision design to minimize adverse impacts to community character, or to the environment, and to mitigate any impacts from other constraints on the land that could not be avoided. Require mitigation actions to remain within the CPA of Bonsall.
- **Policy 2** Buffer residential areas from incompatible activities, which create heavy traffic, noise, dust, unsightly views, or from incompatibility with the surrounding environment.
- Policy 3 Preserve ridgelines by siting buildings below ridges or set back with sufficient distance to minimize visual impacts. Encourage screening to visually shield all structures, including the use of vegetation. And well as appropriate and varied building materials.
- Policy 4 For proposed major subdivisions, require open space easements that first are considered for agricultural or equestrian needs of the Bonsall Community.

Comment: The SP and DEIR cannot avoid the clear violation of these provisions. Adding this project in our planning area is inconsistent with our land use goals and inconsistent with both the GP and CP, the Community Development Model, and the Smart Location requirements of LEED ND. The DEIR must, but does not, explain and analyze the environmental effects of this discrepancy WHY?





Dedicated to enhancing and preserving a rural lifestyle



C. Village Boundaries Map

Comment: The SP and DEIR cannot avoid the clear violation of the existing Map, which shows the village boundaries of two designated rural villages. This project would show three Villages instead of two based on the community model the resulting conflicts with numerous other GP and CP provisions. *The DEIR must, but does not, explain and analyze the environmental effects of this discrepancy.*

Community Conservation and Protection

Each policy addresses a characteristic of slope or soil type which acts as a constraint to development. For each constraint that a particular project site contains, the project must offer a compensating benefit, designed to ameliorate the immediate impacts of the project and provide overall benefits to the community. These benefits are of two types; limitations on grading for residential building pads, and dedications of material open space easements, agriculture or equestrian easements over certain areas on the site. Limitations on pad grading provide benefits in terms of visual impacts, reduced storm runoff and reduced removal of soil in rocky areas which are difficult to re-vegetate.

- Policy 1 Require grading to be contoured to blend with natural topography, rather than consist of straight edges.
- Policy 2 Restrict, to the maximum extent feasible, extensive grading for development projects in areas with slopes that are 20 percent or greater, in order to preserve and protect the environment, and to lessen grading and erosion.
- Policy 3 Require development on slopes to be stepped to follow and preserve topography to the maximum extent feasible.
- Policy 4 Minimize cut and gill grading for roads and access ways to the absolute minimum necessary.

Policy 5 Allow further reductions in minimum lot sizes indicated in Policy LU-5.2.1, through Planned Development, Lot Area Averaging, or Specific Plan projects only when setbacks, building scale, and design are appropriate to retain the equestrian and agricultural community character in the area.

This project does not meet the Lot area Averaging and Planned Residential with specific findings.





Dedicated to enhancing and preserving a rural lifestyle



Agricultural soils and production

Policy 1 Encourage the protection of areas designated for agricultural activities from scattered and incompatible urban intrusions, along with the provision of greenbelt/buffers between agricultural zoning and urban zoning.

Policy 2 Require development to minimize potential conflicts with adjacent agricultural operations, through the incorporation of adequate buffers, setbacks, and project design measures to protect surrounding agriculture and support local and state right-to-farm regulations.

Comment: Neither the SP nor the DEIR is clear as to which design standards apply. The SP purports to override all county documents and states it prevails over any inconsistent provisions in the GP, CP, ordinances or design guidelines. In other places it states some aspect of the project is consistent with the Bonsall and VC Design Guidelines, implying that they would, nevertheless, be applicable. The many pictures, instead of clear text, clearly show urbanized design, out of scale and character for a rural community. The massive grading replaces natural hills with manufactured slopes to accommodate urban design, ignoring natural topography for both roads and residences. The request for deviations from road standards is also in direct conflict with these provisions in the Community Plan. The DEIR must, but does not, explain and analyze the environmental effects of these discrepancies.

Commercial Goals

- Policy 1 Require the design of commercial development to enhance the character of a rural village and not take on an urban type design.
- Policy 2 Require commercial development to be compatible with the rural environment and enhance the community's quality of life. Require all commercial uses to have aesthetically pleasing and functionally adequate operations with appropriate onsite parking, internal circulation setbacks, and landscaping; and not cause any adverse impacts on neighborhood properties.
- Policy 3 Discourage incompatible land uses on areas of agricultural use and land suitable for agricultural Usage.
- Policy 4 Require commercial development to provide buffers between adjacent residential areas, this can be accomplished through increased setbacks or other techniques such as grade differentials, walls and/or landscaping.

Comment: Neither the SP nor the DEIR deals with the fundamental fact that the CP establishes commercial uses only in the two existing Villages, and eliminates commercial uses elsewhere, consistent with smart growth principles and the Community Development Model. The Semi-Rural Land Use Designation for the Project Site is required by both the GP and SP to remain so. *The DEIR must, but does not, explain and analyze the environmental effects of this discrepancy Why?*





Dedicated to enhancing and preserving a rural lifestyle Agricultural Goals



Agricultural goals are supported through out every element of the Bonsall Community Plan.

Comment: Neither the SP nor the DEIR addresses this major thrust of both the GP and CP to "support" Agriculture, not destroy it. *The DEIR must, but does not, explain and analyze the environmental effects of this discrepancy.*

G. Mobility Goals

Goal: Scenic routes where community character and natural resources are preserved by minimizing the impacts of public or private development along roadways in Bonsall.

Circulation and Mobility

Policy 1 Minimize the use of cul-de-sacs in the Bonsall CPA and require new subdivisions to provide local connectivity by providing linkages for long-term circulation improvement.

Comment: As noted above, neither the SP nor the DEIR is clear as to which design standards apply. There appears to have been no consideration of whether this Project can provide two separate LEGAL access points to public roads or if other public roads within the project would provide a clear circulation need that benefits the entire community are needed (to replace proposed private roads. The massive grading proposed seems a clear violation of the requirement for minimizing altering the landscape and following existing natural topography as stated before in the Bonsall policies and goals. The DEIR must, but does not, explain and analyze the environmental effects of these discrepancies WHY?

Fire Protection Goals

Bonsall has fire supression coverage from three separate agencies Vista Fire Protection District, North County Fire Protection District and Deer Springs Fire Protection District. We support the district's decision to object to unsafe building.

Comment: The continued objections of the Deer Springs Fire District to this Project negate compliance with this requirement, yet the SP and DEIR continue blithely on, as if no objections or deficiencies exist. *The DEIR must, but does not, explain and analyze the environmental effects of this discrepancy WHY?*

School Facilities

The Bonsall Sponsor Group works closely with the school district coordinating school facility planning with residential development to ensure that school facilities will be available to accommodate the increase in enrollment without overcrowding."

Comment: No school district has accepted the possible additional students generated by the Project. The residential construction will precede, not be coincident with, school construction. The potential school site is conditioned to be turned into additional residences if not accepted by a school district. **The DEIR must, but does not, explain and analyze the environmental effects of these discrepancies.**





Dedicated to enhancing and preserving a rural lifestyle



Open Space Goals

Policy 1 Support low intensity land use zoning in undeveloped mapped floodplains, such as agricultural and low density residential zoning, to protect downstream areas from flooding hazards to minimize impacts on wildlife habitat and to provide scenic open space.

Comment: The SP only tentatively designates a 12-acre public park site. The Project minimally meets the PLDO ordinance 3-acres per 1,000 population requirement, falling woefully short of the 10-acres per 1,000 GP goal for parks. At least 350 homes will be constructed and occupied before any parks, public or private. The SP makes no provision for construction of park amenities, just dedication of raw land. Overall Project site planning appears to destroy any existing connectivity for animal migration, instead of creating or maintaining a functional open space system. The design is to create an isolated urbanized compound totally unrelated to its surroundings. This will be a closed community of urban sprawl, not one with "openness and access to surrounding open space." **The DEIR must, but does not, explain and analyze the environmental effects of these discrepancies WHY?**

- 1. BOTH the Specific Plan and the DEIR for the project fail to substantiate consistency with CEQA or consistency with the San Diego GP policies that would justify exemption of this project from prohibition of Leap Frog Development, that the DEIR fails to disclose environmental impacts and/or provide adequate mitigation for this project.
- 2. Decision makers and the public are deprived of this essential information which is required by CEQA.
- 3. These failures require re-circulation of a revised DEIR that addresses them.

By way of brief summary, the County has failed to include assessment of Impact areas which are directly related to the proposed LHR Project Noise generation. The Noise analysis was not performed for these Noise Sensitive Land Uses (NSLUs), Environmental Impact is impossible to assess. There are contradictory values for projected Community Noise Evaluation Level (CNEL) values presented without reconciliation of the differing values.

August 16, 2013 Darnell Associates Independent Expert review of the Chen Ryan Traffic Impact Study presents factual evidence that the Chen Ryan Traffic Impact Study understated the Traffic volume and distribution. The reliance on the deficient Chen Ryan Traffic information directly affects the Noise modeling employed by Recon resulting in inaccurate Traffic Generated Noise levels.

Significant potential Impacts outside the Subdivision boundaries are not evaluated, or properly evaluated and need to be. *When will this happen?*





Dedicated to enhancing and preserving a rural lifestyle



Impacted existing NSLU's not evaluated for Noise Impacts

TABLE 12 – "FUTURE OFF-SITE NOISE LEVELS AT SPECIFIC LOCAL RECEIVER LOCATIONS" p. 47 of the Noise Report has errors and exclusions of key existing NSLU's. Every Assessor Parcel Number (APN) listed in the Table is incorrect. Please correct this deficiency. Also, Figures 6a and 6b geo-locate On-Site Local Receiver locations, and provide a reference back to Table 12. Figure 7 for Off-Site Local Receivers does not label Local Receivers with a reference back to Table 12. Remedy this by labeling Figure 7 Off-Site Receivers with a reference back to Table 12. Also, include a Table in similar format to Table 9 which cross references Off-Site Local Receivers to map locations.

Rodriguez Private Road is indicated on Sheet 9 of 9 of the Tentative Parcel Map. Rodriguez Road is being improved to a 24' paved surface. Consequently, the Traffic Study should indicate the traffic volume and the Noise Report should assess Traffic Generated Noise for all NSLU's along the route of Rodriguez Road. There is no indication in the discussion beginning at page 47 of the Noise Report that the Noise Impacts of Rodriguez Private Road increased traffic volume directly related to the proposed LHR Project was assessed. Please discuss specifically if and how Rodriquez Road is included in the Noise modeling results.

The following NSLU's on the eastern border of Rodriguez Road were not included as Specific Local Receivers in Table 12 "Future Off-Site Noise Levels at Specific Local Receiver Locations" p.47 of the Noise Report:

APN 129-190-37-00

APN 129-190-30-00

APN 129-380-01-00

Were these NSLU's assessed as Local Receivers? If not, why were these residential NSLU's omitted from analysis?

Contradictory CNEL Values for the same Local Receiver Location

Table 12 at p. 47 of the Noise Report specifies a predicted future Noise Level of 54 CNEL for 128-290-77-00 (APN corrected to proper value from the erroneous value in Table 12). This Assessor Parcel Number corresponds to the existing residence at 9550 Covey Lane.

Table 13 (page not numbered) "TABLE 13 - CUMULATIVE OFF-SITE TRAFFIC CNEL AT 100 FEET FROM CENTERLINE lists an existing value of 44.2 CNEL and a LHR Project Build out value of 55.7 CNEL at the LHR project eastern boundary, which is approximately 190 feet from the property line of the 9550 Covey Lane NSLU.

Cumulatively Significant Noise Impacts p, 56 "The nearest residence to the future centerline of Lilac Hills Ranch Road is approximately 200 feet to the west and 50 feet north of Covey Lane, which would result in a combined noise level of 61 CNEL at the building façade." This location is the residence at 9550 Covey Lane. There is a conflict with the cumulative CNEL value as presented in the text on Page 56 with Table 13's value. Which value is correct?





Dedicated to enhancing and preserving a rural lifestyle

Evaluation of Existing Noise Conditions

Please discuss and justify the following regarding the baseline Existing Noise Condition Wednesday, July 25, 2012 between 11am and 3:30 PM:

- 1. *Why were only 8 locations evaluated?* Please justify the adequacy of the 8 location sample size to construct a rational baseline for the project.
- 2. Please elaborate in detail the rationale for each of the 8 site locations selected.
- 3. Please elaborate in detail and justify the use of 15 minute mid-afternoon single samples as an adequate baseline for establishing Existing Noise Conditions.

Traffic Generated Noise Analysis relies on the June 28, 2013 Chen Ryan Traffic Impact Study

Table 12 - "FUTURE OFF-SITE NOISE LEVELS AT SPECIFIC LOCAL RECEIVER

LOCATIONS" p. 47 of Noise Report is presented as the basis for ADT traffic volume for modeling the LHR project Traffic Generated Noise.

The August 16, 2013 Darnell Associates Independent Expert review of the Chen Ryan Traffic Impact Study submitted as Public Comments for the LHR DEIR presents factual evidence that the Chen Ryan Traffic Impact Study (TIS) understated the Traffic volume and distribution.

In summary, the Chen Ryan TIS understated ADT trip generation 11.9%. Additionally, Chen Ryan overstated internal trip capture, which would change ADT distribution assignment to area roads. Further, the Darnell August 16, 2013 Independent Study assigns far greater traffic volume to Mountain Ridge and Covey Lane Private Roads, where a large population of Offsite NSLU receivers are located. The reliance on the deficient Chen Ryan Traffic information directly affects the Noise modeling employed by Recon resulting in inaccurate modeling of Traffic Generated Noise levels. Fact based assessment of Noise Impacts mandates revision of the Chen Ryan Traffic Impact Study, and corresponding revision of the Traffic Generated Noise modeling from RECON.

Impacts outside the Subdivision Boundaries

The 60 CNEL Noise Level Contour Graphic needs to be extended to include the Off-Site Impacts for ALL of the Projects Secondary Access Roads:

- Mountain Ridge from the Subdivision boundary to Circle R Drive
- Covey Lane from the Subdivision eastern boundary to West Lilac Road
- Rodriguez Road to Covey Lane

Noise and the Noise Report.

For example, DEIR Subchapter 2.8 – Noise 2.8.2.1 Issue 1: Traffic Generated Noise p.28 -8:

"Existing receivers along Mountain Ridge Road south of the project site would experience a potentially substantial increase in ambient noise levels of 8 CNEL, however, noise levels within 100 feet of the roadway centerline would be 53 CNEL or less."

When Mountain Ridge Private Road traffic volume is increased to the levels indicated in Extend 60 CNEL Contours Offsite

- Mountain Ridge to Circle R
- Covey Lane to West Lilac
- Rodriguez Road to Covey Lane





Dedicated to enhancing and preserving a rural lifestyle



the August 16, 2013 Darnell Associates Independent Expert Review, and the 60 CNEL Noise Level Contour line is plotted on Mountain Ridge, in excess of 60 CNEL will be indicated at the residential façade at 31013 Mountain Ridge (APN 129-430-13-00).

Summary

DEIR Subchapter 2.8 – Noise and the Noise Report have many significant errors and omissions, and the reports rely on the flawed LHR Traffic Impact Study. Informed Environmental Analysis is impossible to perform with this flawed information.

Please revise DEIR Subchapter 2.8 and the Noise Report and notice and recirculate for Public Comment.

Submitted by:

Margarette Morgan, Chair Bonsall Sponsor Group





Dedicated to enhancing and preserving a rural lifestyle



August 17, 2013

TO: Mark Slovick, Planning Manager, Lilac Hills Ranch Project
Department of Planning & Development Services County of San Diego

FROM: The Bonsall Sponsor Group

RE: Accretive Investment Group proposal DEIR –DEIR Public Comment to the Proposed Accretive Lilac Hills Ranch General Plan Amendment and Specific Plan PDS2012-3800-12-001(GPA),PDS2012-3810-12-001 (SP)

Executive Summary: Lilac Hills Ranch DEIR Responses

The Bonsall Community Sponsor Group has been grappling with this project over many months. In our minds it is a bad ill conceived community busting project that should never have been brought forth to be examined in the light of day. Both the Bonsall and Valley Center planning groups have invested too many hours in trying to analyze a project that has so many flaws that more questions have been created than can possibly ever be plausibly answered.

The applicant has a penchant for putting off the preparation of necessary plans until sometime after the Project is approved and out of the reach of the public and the entitlements are awarded. This is like buying a pig in a poke.

The arcane formula that establishes how each jurisdiction determines how sacrificed wetlands will be mitigated and to what extent, apparently results in a straw drawing contest, and the agency that presents the longest straw sets the required acreage for mitigation, they are not additive.

Planning groups have more things to do than analyzing what can be considered a make work project, instigated by a rouge developer, of this nature. We are surprised that a developer would propose such an ill conceived improperly designed project for any kind of serious consideration. In our minds the associated developer of this project proposal has lost all creditability to the point that future projects proposed by this firm should be rejected out of hand and placed in the round file before any serious money or time is spent to analyze and process them.

The Valley Center Planning Group and the Bonsall Sponsor Group has spent many hours analyzing this project. We, therefore, without hesitation endorse all findings by the Valley Center Planning Group and their extensive analysis and conclusions concerning the project. Valley Center has done a monumental job they should be congratulated on many levels for their sense of community duty in doing what is a most unrewarding job.

Several things should be reiterated and reemphasized that Valley Center has so ably discussed:

Specifically how this project will negatively impact Bonsall, and how justification for the project is found particularly weak by the Bonsall Community Sponsor Group will be discussed in the remainder of the summary comments.

You will find that some of the text to be similar to Valley Center's submission however, Bonsall has many more questions and they are highlighted in bold and italics for easy reading in the 56 page document.

We agree with Valley Center in the following statements:





Dedicated to enhancing and preserving a rural lifestyle



A. Introduction

This Executive Summary is intended to aid reviewers of the comments on the Lilac Hills Ranch Draft Environmental Impact Report [DEIR] submitted by the Bonsall Sponsor Group. The review of the DEIR prepared by the County Department of Planning and Development Services, the Lilac Hills Ranch Specific Plan prepared by the applicant, and many technical reports that are the basis of the DEIR prepared by various consultants, has generated a significant volume of comments. The thousands of pages that make up the DEIR documents and their sometimes very technical nature made it difficult for volunteers to review and respond to every item in the relatively short time allowed. However, the principle issues are addressed in some detail in the responses that accompany this summary.

This summary should not substitute for the detailed comments and analyses presented in the attached comment documents.

Project Objectives – The following excerpt from the DEIR summarizes the Project Objectives:

PROJECT DESCRIPTION, LOCATION, AND ENVIRONMENTAL SETTING

1.1 Project Objectives

The proposed project is based on a wide range of reports that studied the different constraints and opportunities involving the project in concert with the County of San Diego and local community issues. The general components of the proposed project were determined using the project objectives described below.

- Develop a community within northern San Diego County in close proximity to a major transportation corridor consistent with the County's Community Development Model for a walkable pedestrian-oriented mixed-use community.
- 2. Provide a range of housing and lifestyle opportunities in a manner that encourages walking and riding bikes and that provides public services and facilities that are accessible to residents of both the community and the surrounding area.
- 3. Provide a variety of recreational opportunities including parks for active and passive activities, and trails available to the public that connect the residential neighborhoods to the town and neighborhood centers.
- 4. Integrate major physical features into the project design, including major drainages, and woodlands creating a hydrologically sensitive community in order to reduce urban runoff.
- 5. Preserve sensitive natural resources by setting aside land within a planned and integrated preserve area.





Dedicated to enhancing and preserving a rural lifestyle



- 6. Accommodate future population growth in San Diego County by providing a range of diverse housing types, including mixed-use and senior housing.
- 7. Provide the opportunity for residents to increase the recycling of waste.
- 8. Provide a broad range of educational, recreational, and social uses and economically viable commercial opportunities within a walkable distance from the residential uses.

The County has structured the Objectives of the EIR, in aggregate, so narrowly that only the Lilac Hills Ranch Project, as proposed by the applicant, can fulfill the Project Objectives, leading to a self-serving and biased environmental analysis. The Bonsall response takes exception to the implied claims that the Project meets all of its own objectives and suggests that other alternatives to the proposed Project may fit the objectives better.

Objective One

The County has structured Objective One of the EIR so narrowly that only the Lilac Hills Ranch Project can fulfill this Project Objective, leading to a self-serving and biased environmental analysis.

Objective Two

The Project does not meet its own objective for Objective Two.

Objective Three

We do not have any issues with this objective other than to state that any Project required to have a Discretionary Permit approved would have to comply with this objective.

Objective Four

The Project does not meet its own objective for Objective Four.

Objective Five

We do not have any issues with this Objective other than to state that any project required to have a Discretionary Permit approved would have to comply with this objective.

Objective Six

The County has structured the sixth Objective of the EIR so narrowly that only the Lilac Hills Ranch Project can fulfill this Project Objective, leading to a self-serving and biased environmental analysis.

Objective Seven

Any Project Alternative would comply with this Objective equally.

Objective Eight

This objective is subjective and could be met by developing the Project at General Plan densities, which would preserve existing agricultural businesses and residential-based businesses.

2. Project Inconsistencies with Regional and General Plans

In comments submitted over the last year, the Bonsall Sponsor Group and the Bonsall Design Review Board one and the same in our case have challenged the proponent's assertions that this SP/GPA is consistent with the adopted County General Plan [GP], or with Bonsall's [CP], or with the Bonsall Design Guidelines.

Page 3-15

Dedicated to enhancing and preserving a rural lifestyle



Our previous comments, which have previously been accepted but if requested will be sent again via email, have also challenged the logic exhibited throughout Accretive Investment Group's Specific Plan and now in their Draft Environmental Impact Report (DEIR): that amending a particular GP Regional Category to suit the project somehow also reconciles the project's inconsistencies with a wide array of General and Community Plan Goals and Policies.

The proposed SP/GPA is inconsistent in broad and fundamental ways with the San Diego County General Plan and Community Plans of both Bonsall and Valley Center. Further, the DEIR fails to disclose and analyze these broad and fundamental inconsistencies and their environmental consequences as CEQA requires. The DEIR is derelict in concluding as it does that: "Overall the project would be consistent with the General Plan; therefore land use impacts associated with policy inconsistencies would be less than significant" (Chapter 3 Environmental Effects Found Not To Be Significant (p 3-65).

This DEIR fails to perform the analyses required for decision makers, first, to understand the parameters of this proposal, and, second, to appreciate the nature and reach of its impacts. The DEIR does not even have a rudimentary analysis of Consistency with the General Plan.

Internal consistency is required of all County General Plans by California State Law. Therefore, in considering a Specific Plan, particularly one that requires amendments to an adopted General Plan, it is crucial to understand exactly where the Specific Plan is inconsistent with General Plan regional categories, land use designations and road classifications, principles, elements, goals and policies.

A Specific Plan is an implementation vehicle. Approval requires compliance with CEQA; consistency as well with the web of interconnected and mutually-supporting elements of the County General Plan, and consistency with the array of implementation actions, strategies and procedures that are in place to achieve the goals and policies that the General Plan sets forth. Inconsistency requires denial of the project OR adapting the General Plan to fit the Specific Plan – the tail wagging the dog. Changes of this magnitude (Land Use Policies, Mobility and Safety Elements) to the August 3, 2011 San Diego County General Plan would require revisiting the Environmental Impact of the San Diego County General Plan and likely invalidates the San Diego County General Plan. Broad and fundamental amendments to adopted General and Community plans would require countywide environmental review.

We all can understand why the applicants might want to avoid disclosing the array of GP and CP Goals and Policies that this project violates. But CEQA's purpose is not to gloss over or obscure inconsistencies in order to ease approval of this project. CEQA's purpose is disclosure. Therefore, the DEIR for this SP/GPA must reckon specifically and individually with the General Plan Vision and Guiding Principles and the reflection of these in the Community Development Model, as well as with Goals and Policies across the GP's seven elements: Land Use, Mobility, Conservation and Open Space, Housing, Safety and Noise; as well as goals and policies of the Bonsall and Valley Center Community Plans.





Dedicated to enhancing and preserving a rural lifestyle



Once inconsistencies are disclosed there are only three ways to resolve them: reject the project, re-design the project, or re-build the County General Plan to suit these applicants. <u>Inconsistencies with General and Community Plans, Design Guidelines and other ordinances and policies are NOT subordinate to this project's Specific Plan, as the Specific Plan asserts.</u>

Bonsall votes for the first REJECT THE PROJECT based on all of the inconsistencies.

The full text of the General Plan and Community Plan Inconsistencies comments does an exhaustive analysis of several of the General Plan and Community Plan goals and policies to reveal the inadequacies of the proposed Project and the premise being advanced to allow its approval.

1. Transportation/Traffic

The Bonsall Sponsor Group endorses the endorses the comments submitted by Darnell Associates regarding traffic impacts provided to us by the Valley Center Planning Group with our thanks.

2. Agricultural Resources

The Bonsall Sponsor Group endorses the comments submitted by the Cleveland National Forest Foundation regarding agricultural impacts.

3. Biological Resources

The DEIR cites three sensitive plant species observed on the Project site as well as observations of 13 Group 1 animal species ranging from lizards, snakes and jackrabbits to raptors, passerine birds and mule deer. Beyond the cited plants and animals, the DEIR notes the projected significant loss of several native plant habitats with special importance for the cited animal species and others such as mixed southern chaparral and coastal sage scrub.

The DEIR indicates that these significant losses can be mitigated off-site through the purchase of land within the draft PAMA based on a formula developed by the County. However, the DEIR does not account for the loss of 608-acres of raptor foraging area, which includes both natural vegetation formations and agricultural lands. The proposal is to set aside 81-acres off-site for raptor foraging calculated using the losses of sensitive native vegetation. It does not include in that calculation the lost agricultural land foraging area.

The DEIR suggests that the impacts to the three sensitive plants and 13 sensitive animals [and we assume the resident plants and animals not judged to be sensitive] are less than significant once mitigated, saying that none of the cited species represent significant populations or significant portions of regional populations. And yet, the DEIR and Biological Resources Report offer no data to support those claims. Nor, do they offer data that show the local population densities of the cited species that can be compared to regional population densities.





Dedicated to enhancing and preserving a rural lifestyle

The DEIR notes that the riparian habitats on the Project site will be preserved in open space easements. Those portions of the riparian habitats destroyed by road crossings will be recreated on-site adjacent to the preserved existing habitats. However, the DEIR gives short shrift to the edge effects it acknowledges [e.g. human intrusion, invasive plant species, domestic pets, noise, night light, etc.] pointing to fences and signage and weeding efforts managed by an undetermined manager.

The DEIR does not adequately account for the cumulative effects stemming from the impacts to the Project site. If we take San Diego County as the 'region' or even North San Diego County as the region, we should be looking at the historic extent of coastal sage scrub, southern mixed chaparral, southern coast live oak riparian woodland, coast live oak woodland, southern willow scrub, southern willow riparian woodland, and wetlands within that area compared to what exists today. We should then ask to what extent have these vegetation communities been extirpated and to what extent the remaining examples of those communities have significance. Comparing proposed destruction in one project with destruction that has or will result in a handful of other smaller projects isn't an effective measurement of cumulative effects.

4. Cultural Resources

The DEIR and Cultural Resources Report address historic cultural sites on the Project site individually. They fail to regard the Project site overall in the context of nearby significant Native American village sites along the San Luis Rey River and its tributary, Moosa Creek. The Project site is rich with artifacts and occupation sites, but the proposed mitigation and preservation procedures appear to be piecemeal for a Project as large and transformative as this one.

The grading, by cut and fill techniques, of 4-million cubic yards of earth will jeopardize the opportunity for future study and appreciation of the basic integrity of the cultural significance of the larger area. There are suggestions in previous studies that an as yet undiscovered earlier human habitation of the Project site area, or a separate village from those already known may be present.

There are also concerns about the data recovery program and its methodology. Most of the previous studies of the area are 35 years old and more current studies may be needed to fully understand the significance of the site.

5. Hazards, Hazardous Materials, Wildfires

The development of the densely packed Project adjacent to agricultural areas presents the need to buffer those agricultural areas from the development and its sensitive receptors [schools, churches, senior centers, parks, homes]. However, there is no discussion in this subchapter of General Plan policy S-11.5, which requires development adjacent to agricultural operations in Semi-rural and Rural lands to adequately buffer agricultural areas and ensure compliance with relevant safety and codes where hazardous materials are used. Please note that the Bonsall Community Plan has policies regarding buffering and chapter and verse on the protection of the agricultural areas of our community.





Dedicated to enhancing and preserving a rural lifestyle



The issues of emergency response and evacuation plans are troublesome for this Project. The Evacuation Plan does not address the most fundamental evacuation issue of the proposed Project – the limited number of roads for automobile evacuation of the 5185 residents of the proposed Project. The mobility element roads nearest the Project are West Lilac and Circle R Roads. Both roads were built as 2.2 E two-lane roads to serve a rural community with small, rural populations and the applicant plans no upgrades to these roads. The addition of 5000+ people at the Project site will severely impact both emergency response and evacuation during a crisis event, exacerbating already congested conditions in such circumstances and putting many people at risk.

The applicant would further impact evacuation plans by proposing 10 road standard modifications that would lower the classification of the mobility element roads in some cases and lower the design speeds of those roads. With lower design speeds and narrower roadways, the Project will imperil evacuations from Bonsall and Valley Center to the I-15 corridor by existing residents, and impede the prospective residents of the Project at the same time. This kind of impact, played out in scenarios like Bonsall and Valley Center experienced in 2003 and 2007, would severely and significantly put hundreds of people at risk. Further, the Project has but a single evacuation route to the East. That is the easterly section of West Lilac Road that connects to Lilac Road. It is a Circulation Element 2.2 E two lane rural road. There are no plans to upgrade this road. If an evacuation event is caused by a large wildfire from the west, the ensuing smoke plume will result in a panic evacuation over a single treacherous road.

The Project has <u>not</u> demonstrated that the project can meet the 5-minute Emergency Response requirement for Fire Services. The proposed solutions of building a fourth fire station in the Deer Springs Fire Protection District [DSFPD] at the Project site do not work from the perspective of jurisdictional issues and fiscal operational cost issues. None of the existing fire stations in the DSFPD meet the 5-minute requirement.

The Project is proposed for a site in a very high fire hazard severity zone [FHSZ]. Locating a Project of this size and scope in a very high FHSZ is not a smart location that is consistent with preventive land use planning. The DEIR states that failure to meet the standard 100-foot Fuel Modification Zone [FMZ] for significant portions of the Project would be a significant impact. Section 5.4 Fuel Management Zones on page 42 of the FPP states "The project includes a few areas where fuel modification zones are less than 100 feet wide. Based on even a quick scan of Figure 1.6 from Chapter 1 of the DEIR (Attachment H), the more accurate and true statement is: The project includes extensive areas where fuel management zones are less than 100 feet wide. This is a severe design flaw.





Dedicated to enhancing and preserving a rural lifestyle



Fire Protection Plan (FPP)

The proposed Project FPP does not meet the following basic requirements identified below by Issue Number:

- 1. Of the three Fire Station site Options proposed by the Applicant, none meet the minimum acceptance criteria of the Deer Springs Fire Protection District (DSFPD). The Charter of the DSFPD focuses on providing no greater than 5-minute emergency response time to the ENTIRE DSFPD, of which the proposed LHR Project is a subset.
- 2. The Applicant states in the FPP that the LHR Project fully complies with the DSFPD Ordinance No. 2010-01, County of San Diego Consolidated Fire Code, and County of San Diego Public and Private Road Standards. *The LHR has factual compliance issues with all of these regulations*.
- 3. The FPP focuses nearly exclusively on Wildfire Management and does not sufficiently address either Structure Fires or Emergency Medical Service (EMS).
- 4. The FPP doesn't adequately address and analyze the Environmental Impact of the use of six electronic road gates on fire access roads.

Fuel Modification Zones (FMZ) – The applicant appears to rely on other property owners outside the LHR Subdivision boundaries to comply with the 100 foot FMZ requirement.

Thus, the proposal amounts to putting a large project with several vulnerable populations into a very high fire hazard severity zone with substandard fuel modification zones and depending on more rigorous construction techniques to restore a margin of fire safety. The question becomes why the applicant hasn't redesigned the Project to allow for standard FMZs throughout the Project? This problem is strained further by uncertain access to the Project site by fire apparatus. That access depends on at least two private roads, for which easement access is uncertain, and the applicant's proposal to gate those access points. These constraints on access are problematic for fire safety and evacuation efficiency.

Significant Irreversible Environmental Changes Resultant from Project Implementation

The proposed Project [Lilac Hills Ranch] will cause significant, irreversible, and, in most instances, immitigable impacts to the Project site, to the Valley Center and Bonsall communities and their community plans and to the County of San Diego and its General Plan. The Project will require amendments to the General Plan, its principles, policies, and regional land use designations and to the Bonsall and Valley Center Community Plans, or, at least, a severely disfigured interpretation of all of them.

The DEIR focuses on the grading of the Project site, on the use of fuels [energy] to prepare the Project site and manufacture construction materials, on the consumption of construction materials [wood, concrete, asphalt, drywall, etc.], on subsequent energy and natural resource consumption by the eventual residents, and on the amount of time to construct the project.





Dedicated to enhancing and preserving a rural lifestyle The movement of over 4-million cubic yards of dirt and rock on the Project site is perhaps obvious irreversible impact. Another is the loss of hundreds of acres of productive agricult



Another is the loss of significant amounts of biological habitat and the flora and fauna that presently occupy them. The DEIR does not adequately address the cumulative impact of scores of such individual losses caused by multiple projects within the County and the irreversible loss of the majority of native habitats in the aggregation of those individual losses.

Less obvious losses are the changes to the General Plan and related Community Plans that will be required for this Project to be approved. Those changes will dramatically alter the parameters of the General Plan that strive for smart growth. And, if the Project is approved, it will set a precedent that will have severe ramifications across the unincorporated countryside of San Diego County.

Greenhouse Gases

The Bonsall Sponsor Group endorses the comments submitted by the Cleveland National Forest Foundation regarding Greenhouse Gas impacts.

Water Quality/Hydrology

The DEIR concludes under Issue 1: Water Quality Standards and Requirements in Chapter 3.0 "Environmental Effects Found Not to be Significant" as follows:

"Through these design features, including the use of permeable pavers, the project would not result in the violation of any water quality standards or waste discharge requirements. Impacts associated with this issue would be less than significant."

We strongly disagree with this finding and conclude that there is high likelihood of potentially significant and immitigable impacts.

Off-site routes for recycled water and sewer pipelines have been found to lack sufficient legal right-ofway easements as represented in figure 3-4, "Off-site Sewer Collection System." This determination is confirmed by Valley Center Municipal Water District [VCMWD] in a letter labeled Attachment A. This finding makes construction of sewer and recycled water pipelines for the Project problematic.

Use of the Lower Moosa Water Reclamation Facility [LMWRF] for a series of alternative sewage solutions has been proposed. The LMWRF was built in 1974 and provides disinfected secondary treatment of reclaimed water only. It has been approved by two agencies to double the LMWRF capacity to 1.0 million gallons/day [MGD] of influent. That capacity is not presently added.

http://www.sdcounty.ca.gov/pds/Groups/Bonsall.html







Dedicated to enhancing and preserving a rural lifestyle



It appears that the Hydro Modification Design is relying on exaggerated assumptions for both rainwater harvesting success and the availability of residential landscape areas as permeable surfaces for absorption of water. That same design also reveals the desire to install 23 acres of private roads paved with permeable pavers to permit additional percolation of water into the soil. Such roads may fail under the weight of a Type 1 fire engine.

It is tortured logic to argue that taking green field agricultural and semi rural estate land and introducing a dense urban environment that develops 504 of the 608 acres, adding 83 acres of road and 68 acres of manufactured slopes is consistent with policy COS-5.2 which requires development to minimize the use of impervious surfaces.

Geology and Supplemental Geology Report

The review identifies questions regarding the need for blasting that cannot be quantified to determine the amount and length of time needed to do removals and ultimately placement of fills. Silicates will be a potential hazard relative to the AQMD standards.

Slope Stability and Remediation describe cut slopes 6.2.1 and fill (manufactured) slopes 6.2.2 in excess of seventy-feet (70-feet) in height. There are no seventy-foot high manufactured slopes existing in this community, which makes these proposed slopes out of character with the community.

Project Alternatives

The Lilac Hills Ranch Project Alternatives from Chapter 4.0 of the DEIR are below:

- 1. No Project/No Development Alternative
- 2. No Project / Existing Legal Lot Alternative (49 EDU + no commercial)
- 3. General Plan Consistent Alternative (110 EDU + no commercial)
- 4. Reduced Footprint Alternative (1251 EDU + 6 acres of commercial)
- 5. Reduced Intensity Alternative (881 EDU + 5.6 acres of commercial)
- 6. 2.2C (Hybrid) Alternative (1365 EDU + 15.3 acres of commercial


The County's Project Alternatives Analysis in Chapter 4 of the DEIR is grossly defective in meeting CEQA requirements in five areas that are summarized below:

- 1. The DEIR Objectives against which the Alternatives are judged for Environmental Impacts are biased and should be changed to equitable objectives, from which compliance against can be fairly measured.
- 2. The Project does not meet its own Objectives, when fairly assessed.





Dedicated to enhancing and preserving a rural lifestyle



- 4. The Reduced Footprint, Reduced Intensity, and 2.2 C Hybrid are not valid Alternatives. These three "Alternatives" are density variations of the Project. These Alternatives are also not described in enough detail to provide informed Environmental Impact Analysis. [see table 1]
- 5. The Alternatives were not fairly assessed in the DEIR by the Applicant.
- 6. When all eight Alternatives are fairly assessed, the Downtown Escondido SPA meets more Objectives than the Project or any Alternatives.

	Т	able 1	-S	cant At	tribute	25	of 3 A	iternat	es Provid	ed	
	Project			Redu	ced		Redu	ced			
				Footprint			Intensity		2.2 C (I	2 C (Hybrid)	
	Gross	Units/		Gross	Units/		Gross	Units/	Gross	Units/Sq.	
Land Use	Acreage	Sq. Ft.		Acreage	Sq. Ft.		Acreage	Sq. Ft.	Acreage	Ft.	
Single Family Detached	158.8	903		142.1	783		275.5	881	177.0	792	
Single Family Senior	75.9	468		71.1	468		0		75.9	468	
Single Family Attached	7.9	164		0			0		4.3	105	
Commercial/Mixed Use	15.3	211		6.0			5.6		15.3		
Water Reclamation	2.4			2.4			2.4		2.4		
RF/Trailhead	0.6			0			0.6		0.6		
Detention Basin	9.4			5.4			5.5		5.5		
School Site	12.0			9.0			0		12.0		
Private Recreation	2.0			0			0		2.0		
Group Residential/Care	6.5			0			0		6.5		
Institutional	10.7			10.7			10.7		10.7		
Park - HOA	11.8			10.0			3.0		11.8		
Park - Dedicated to County	12.0			6.0			9.0		12.0		
Biological Open Space	103.6			168.8			102.7		103.6		
Non-circulating Road	45.7			45.7			41.5		43.1		
Circulating Road	37.6			37.6			21.5		30.0		
Common Areas/Agriculture	20.2			20.2			65.0		45.0		
Manufactured Slopes	67.5			67.5			65.0		50.0		
Other/Accretive Math Error*	8.1			5.5			0		0.3		
Total	608.0	1746		608.0	1251		608.0	881	608.0	1365	
		* Ta	* Table 4-1 from DEIR Chapter 4 Project Alternatives has the								
sq. ft. = Square Feet			indicated arithmatic errors								

Table 2, below, rates scoring of Alternatives against the Applicant's biased eight Objectives.





Dedicated to enhancing and preserving a rural lifestyle

TA	ABLE 2 - CO	OMPARISON	TO PROJEC	T OBJECTIV	ES				
	Alternates								
Objectives	Project	Downtown Escondido SPA	No Project/No Development	No Project/Legal Lot	General Plan Consistent		Reduced Intensity		
1 -Develop a community within northern San Diego County in close proximity to a major transportation corridor consistent with the County's Community Development Model for a walkable pedestrian-oriented mixed-use community	No	Yes	No	No	No	No	No	No	
2 - Provide a range of housing and lifestyle opportunities in a manner that encourages walking and riding bikes, and that provides public services and facilities that are accessible to residents of both the community and the surrounding area	No	Yes	No	No	No	No	No	No	
3 - Provide a variety of recreational opportunities including parks for active and passive activities, and trails available to the public that connect the residential neighborhoods to the town and neighborhood centers	Yes	Yes	No	No	Yes	Yes	Yes	Yes	
4 - Integrate major physical features into the project design, including major drainages, and woodlands creating a hydrologically sensitive community in order to reduce urban runoff	No	Yes	No	No	No	No	No	No	
5 - Preserve sensitive natural resources by setting aside land within a planned and integrated preserve area	Yes	N/A	No	No	Yes	Yes	Yes	Yes	
6 - Accommodate future population growth in San Diego County by providing a range of diverse housing types, including mixed-use and senior housing	Yes	Yes	No	No	No	No	No	Yes	
7 - Provide the opportunity for residents to increase the recycling of waste	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	
8 - Provide a broad range of educational, recreational, and social uses and economically viable commercial opportunities within a walkable distance from the residential uses	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	
Total Number of Objectives Met	5/8	7/8	2/8	2/8	4/8	4/8	4/8	5/8	

Clearly, the least Environmental Impact, even to these biased Objectives, is shown in Table 2 to be the Downtown Escondido SPA Alternative.

More importantly, the General Plan alternative must be properly considered by the applicants and County, rather than focus their attention strictly within the boundaries of the Project. Apart from the time and money already spent developing the General Plan [12 years and \$19.6 million], it was designed as a plan for the entirety of the County's unincorporated area while being mindful of the incorporated cities as well. The Lilac Hills Ranch Project is only a single piece of a much larger puzzle.





Dedicated to enhancing and preserving a rural lifestyle



To study this "puzzle piece" is NOT to study the General Plan alternative. This "half-study" misses the underlying logic of the new County General Plan which is, according to the lengthy introduction to the GP, to achieve "sustainable development" with a two-part strategy called Smart Growth.

- I. Part One: Direct new growth to areas where infrastructure already exists (such as the established Village in Valley Center's central valley.
- II. Part Two: Retain agriculture and large parcels for functioning rural lands that clean the air, provide vital watersheds, and support diverse forms of wildlife among other functions.

The plan works ONLY when its two interdependent parts work together.

The Lilac Hills Ranch Project undermines both aspects of this strategy.

The General Plan alternative implements both aspects of this strategy. The only acceptable "study" of the General Plan Alternative is to study it in its entirety. The superior solution will be clear.

Specific Plan

The comments on the Specific Plan include several major concerns:

- 1. The Lilac Hills Ranch Project [the Project] is too large and too dense for Valley Center and Bonsall and it is improperly located. Urban densities are incompatible with the rural, agricultural location in which the Project has been sited.
- 2. Roads and Traffic. The road standard modifications proposed by the Project will downgrade the classification of a mobility element road [West Lilac Road] and will lower the design speeds of several road segments, both public and private. At the same time the Project will add over 5000 people and approximately 20,000 average daily trips to those narrower, slower roads causing congestion and road failure.
- 2. Compliance with the General Plan. The Project's Specific Plan threatens to overturn virtually every element in the County's new General Plan adopted in 2011 after 12 years of discussion, compromise and community involvement, nearly \$20 million in government expenditures and countless hours of effort on the part of local citizens. Approval of this Project will require damaging amendments to the General Plan and the Valley Center and Bonsall Community Plans that will be growth inducing, and "COMMUNITY BUSTING" particularly in the western portion of Valley Center and the eastern portion of Bonsall. If the Project is allowed to proceed, one has to question if there is any development that would be rejected because it violated the principles and policies of the General Plan and Community Plans. In the context of this Project, it is unclear that the General Plan is anything more than a placeholder until the next change is proposed.





Dedicated to enhancing and preserving a rural lifestyle



- 4. Services and Infrastructure Water, Schools, Fire, and Waste Treatment—Infrastructure is expensive. Putting in new roads, adding additional lanes to a bridge, building a fire station, putting up a new school, installing sewer and waste treatment plants and building trails all cost large amounts of money. A principal reason why the General Plan Update strongly favors "compact, town center developments" while stating that it intends to limit "growth in areas without adequate roads, water and sewer service" is because of the demands on the public purse for building and then maintaining these infrastructure items over and over.
- 5. LEED-ND/Sustainable and Walkable Community. This Project still has not meaningfully addressed the requirements for LEED-ND development, although it continues to be described as "expected to meet the standards of the LEED-ND or an equivalent program." There is no equivalent program cited and the Project fails to meet any of the site location and linkage requirements listed in the LEED-ND pre-requisites and standards.

The Project also cites its consistency with the Guiding Principles and the Community Development Model in the General Plan for San Diego County. However, even a cursory examination of those principles and the model show that, rather than being consistent, the Project is conversely inconsistent with both the Guiding Principles and Community Development Model. The 'community' that needs to be addressed is the Bonsall and Valley Center communities, and the Project should be understood as an element of that community. The General Plan presently applies the Community Development Model to the Bonsall and Valley Center community and the zoning and land use patterns within Bonsall and Valley Center are consistent with that model.

6. Agriculture—The General Plan Update of 2011 has set aside the area where The Project would be built as a place for agriculture and other rural and semi rural uses. In contrast to the claims made by the Project applicants, the area is not characterized by historical agricultural activity. It is a present-day agricultural area with a long, continuous history of agriculture. Avocado, citrus, cactus commercial nurseries and other farm operations are located in and around the Project areas. These agricultural uses attract insect and fungal infestations, which mean that aerial spraying is often necessary. Spraying could pose a danger to individuals living in the area. On the other hand, prohibiting spraying would make farming nearly impossible. Building The Project at the planned site would greatly damage many currently productive and successful agricultural operations.





Dedicated to enhancing and preserving a rural lifestyle



7. Twists of meaning and lack of clarity in the plan. One of the most difficult aspects of the Project's Specific Plan is the extent to which it makes misleading claims. They would have us believe that they are building a LEED-ND or equivalent development even though The Project violates nearly all LEED-ND standards for site selection and linkage; that adding 5,000 residents to a rural, agricultural area actually improves traffic over narrow, winding rural roads; that grading and moving 4.4 million cubic yards of earth (enough to build a path 4-feet wide around the equator of Earth) preserves natural resources and habitat for animals.

In addition, after criticizing three previous iterations of the Specific Plan, this version continues to use conditional and indefinite language to describe aspects of the Project that should be, at this stage, unconditional and definite. It seems as if the applicants want us to review and approve a suggestion, or an idea rather than a plan that defines their intentions.

There are many other concerns addressed in the Specific Plan comment document. They range from the size and type of parks in the Project to the Fire Protection Plan, from the Water Reclamation Facility to open space and conservation policies, to circulation elements. There are too many to reasonably relate in this summary.

Submitted by:

Margarette Morgan, Chair Bonsall Sponsor Group



